

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786)315-2590 F (786) 31525-99

www.miamidade.gov/economy

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

DURO-LAST Roofing, Inc. 525 Morley Drive Saginaw, MI 48601

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: DURO-LAST Single Ply PVC Roof Systems over Recover Decks.

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews and revises NOA No. 15-1109.09 and consists of pages 1 through 111. The submitted documentation was reviewed by Jorge L. Acebo.

(MIAMI-DADE COUNTY)
APPROVED

Expir App

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 1 of 111

ROOFING SYSTEM APPROVAL

Category:RoofingSub-Category:Single PlyMaterials:PVCDeck Type:Recover

Maximum Design Pressure: See Specific System Herein

TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

		Test	Product
Product	Dimensions	Specification	Description
Duro-Last Membrane	.037" thick,	ASTM D4434	PVC polymer blend polyester reinforced
	Various widths x		roofing membrane.
	150 ft. rolls		
Duro-Last Membrane	.045" thick,	ASTM D4434	PVC polymer blend polyester reinforced
	Various widths x		roofing membrane
Duro-Last Membrane	100 ft. rolls .057" thick,	ASTM D4434	DVC nalyman bland nalyzatan mainfanaed
Duro-Last Memorane	Various widths x	ASTM D4434	PVC polymer blend polyester reinforced roofing membrane
	100 ft. rolls		Tooming memorane
Duro-Last Designer	.045" thick	ASTM D4434	PVC polymer blend polyester reinforced
Series Membrane	Various widths &		roofing membrane: Rock-Ply & Shingle-Ply.
	lengths		
Duro-Fleece Membrane	.047" thick,.	ASTM D4434	PVC polymer blend polyester reinforced
	Various widths x		fleece backed roofing membrane.
D El 1/ 1	100 ft. rolls	A COTTA & D. 442.4	
Duro-Fleece Membrane	.056" thick, Various widths x	ASTM D4434	PVC polymer blend polyester reinforced
	100 ft. rolls		fleece backed roofing membrane.
Duro-Fleece Membrane	.080" thick	ASTM D4434	PVC polymer blend polyester reinforced
Duro i recce memorane	Various widths x	713111111111111111111111111111111111111	fleece backed roofing membrane.
	65 ft. rolls		
Duro-Fleece Plus	.047" thick, .	ASTM D4434	PVC polymer blend polyester reinforced
Membrane	Various widths x		fleece backed roofing membrane.
	100 ft. rolls		
Duro-Fleece Plus	.056" thick,	ASTM D4434	1 5
Membrane	Various widths x		fleece backed roofing membrane.
Duro-Tuff Membrane	80 ft. rolls .045" thick	ASTM D4434	DVC nalyman bland nalyastan rainforced
Duro-Tuff Memorane	Vaious widths x	ASTM D4434	PVC polymer blend polyester reinforced roofing membrane
	100 ft. rolls		Tooming memorane
Duro-Tuff Membrane	.057" thick	ASTM D4434	PVC polymer blend polyester reinforced
	Various widths x		roofing membrane
	100 ft. rolls		-
Duro-Tuff Membrane	.080" thick	ASTM D4434	PVC polymer blend polyester reinforced
	Various widths x		roofing membrane.
	65 ft. rolls		



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 2 of 111

		Test	Product
Product	Dimensions	Specification	Description
Duro-Last EV	53 mil thick Various widths x 100 ft. rolls	ASTM D4434	PVC polymer blend polyester reinforced roofing membrane with KEE films.
Duro-Last EV	60 mil thick Various widths x 100 ft. rolls	ASTM D4434	PVC polymer blend polyester reinforced roofing membrane with KEE films.
Duro-Last Fascia Bar	1 ³ / ₄ " x 10'; 4" x 10'	Proprietary	Extruded vinyl drip edge with holes punched 8" o.c.
Duro-Last Fascia Bar Cover	1 ³ / ₄ " x 10'; 4" x 10'	Proprietary	Extruded decorative cover for Duro-Last Fascia Bar
Duro-Last Fascia	2" & 4"	TAS 111	Kynar finish Galvalume, 24 ga., cover
Duro-Last Snap Coping	12"	TAS 111	Kynar finish Galvalume, 24 ga., coping
Duro-Last 2-Piece Metal "T-Edge"	N/A	TAS 111	Kynar finish Galvalume, 24 ga., with vinyl skirt
Duro-Last 2-Piece Compression Edge	N/A	TAS 111	Kynar finish Galvalume, 24 ga.
Duro-Last Drip Edge	2" face x 10'; 4" face x 10';	Proprietary	Extruded vinyl drip edge with holes punched 8" o.c.
Duro-Last Two-Way Roof Vents	N/A	Proprietary	Injection molded two-way roof vents with a Duro-Last membrane skirt.
Duro-Last Gravel Stop	2" face x 10'; 4" face x 10';	Proprietary	Extruded vinyl gravel stop with holes punched 8" o.c.
Roof-Trak III Walk Pads	30" x 60" .125" thick	Proprietary	Extruded vinyl walk way pads manufactured from Duro-Last membrane.
Duro-Last WB II Adhesive	5 gal. pail	Proprietary	Polymeric waterborne membrane adhesive.
Duro-Last SB IV	5 gal. pail	Proprietary	Low VOC solvent-based membrane adhesive.
Duro-Fleece Membrane Adhesive	10 gal.	Proprietary	Two-component membrane adhesive.
Duro-Fleece CR-20 Adhesive	Kit covers 2,000 ft ²	Proprietary	Dual component, low-rise polyurethane foam adhesive.
Duro-Last Tab Sealer 4725	5 gal.	Proprietary	Solvent-based contact-bonding agent.
Duro-Blue Separation Slip Sheet	4 mil x 20' x 360'; 4 mil x 20'x 100'	Proprietary	Separation slip sheet produced from coextruded polyethylene film.
Duro-Last Duro-Weave Separation Slip Sheet	2.5 mil thick 12' x 328'	Proprietary	Separation slip sheet produced from high density polyethylene tapes and coated on one side with low density polyethylene
Duro-Last Accessories	Various	ASTM D 4434	Custom fabricated accessories for parapets and penetrations: Curb flashing, Inside & Outside Corner, Scuppers, Drain Boot, Parapet Flashing, Stack Flashing; all for use in the Duro-Last roofing systems.



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 3 of 111

APPROVED INSULATIONS:

TABLE 2

Product Name	Product Description	Manufacturer (With Current NOA)
ACFoam II, ACFoam III, ACFoam IV	Polyisocyanurate foam insulation	Atlas Roofing Corp.
ISO 95+ GL	Polyisocyanurate foam insulation	Firestone Building Products Company, LLC
Cellofoam Type IX EPS Insulation	Type IX Expanded Polystyrene (EPS)	Cellofoam North America, Inc.
Insulfoam EPS, R-TECH Fan Fold	Type IX Expanded Polystyrene (EPS)	Insulfoam a Division of Carlisle Construction Materials, Inc.
Kingspan GreenGuard Insulation Board CM	Extruded polystyrene (XPS)	Kingspan Insulation, LLC
Type X Gypsum	Gypsum with a moisture resistant facer and core.	Generic
DensDeck, DensDeck Prime	Silicon treated gypsum	Georgia-Pacific Gypsum LLC
ENRGY-3, ENRGY-3 25 PSI	Polyisocyanurate foam insulation	Johns Manville
Duro-Guard EPS Ultra-Max, Multi-Max FA-3	Expanded polystyrene Type IX Polyisocyanurate foam insulation	Duro-Last Roofing, Inc. Rmax Operating, LLC
H-Shield, H-Shield CG	Polyisocyanurate foam insulation	Hunter Panels, LLC
SECUROCK Gypsum-Fiber Roof Board	Rigid, gypsum-based board stock	United States Gypsum Corporation
SECUROCK Glass-Mat Roof Board	Gypsum roof board with fiberglass facer	United States Gypsum Corporation
Duro-Fold Underlayment Board	Extruded polystyrene with polypropylene facer.	Duro-Last Roofing, Inc.
Duro-Guard Iso II-H & Tapered, Duro-Guard Iso III-H & Tapered, Duro-Guard Iso HD-H	Polyisocyanurate foam insulation	Duro-Last Roofing, Inc.
Duro-Guard Iso II-A & Tapered, Duro-Guard Iso III-A & Tapered, Duro-Guard Iso HD-A	Polyisocyanurate foam insulation	Duro-Last Roofing, Inc.
Duro-Guard ISO II-G & Tapered	Polyisocyanurate insulation with	Duro-Last Roofing, Inc.
Duro-Guard ISO HD-G	fiberglass reinforced organic facers High density polyisocyanurate insulation with coated fibergalss facers	Duro-Last Roofing, Inc
DEXcell Cement Roof Board	Cementitious Insulation Board	National Gypsum Company
DEXcell FA Glass Mat Roof Board	Coated Gypsum Insulation Board	National Gypsum Company



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 4 of 111

APPROVED FASTENERS:

TABLE 3

Fastener Number	Product Name	Product Description	Dimensions	Manufacturer (With Current NOA)
1.	Duro-Last 3"Metal Plates	Galvalume steel stress plates.	3" square	Duro-Last Roofing, Inc.
2.	Duro-Last Poly-plates	Round plastic stress plates.	2" round	Duro-Last Roofing, Inc.
3.	Polymer GypTec	Glass-filled nylon auger type fastener	Various Lengths	OMG, Inc.
4.	Polymer GypTec Insulation Plates	Galvalume steel stress plates.	3" round	OMG, Inc.
5.	Fluted Nail	Coated Steel fluted shank nail insulation fasteners.	Various Lengths	OMG, Inc.
6.	OMG Plastic Plate	Round plastic stress plates.	3" round	OMG, Inc.
7.	Duro-Last #15 Extra Heavy Duty Drill Point Fastener	Corrosion resistant, drill point with a #3 Phillips truss head	Various Lengths	Duro-Last Roofing, Inc.
8.	Duro-Last #14 Concrete Screws	Corrosion resistant, drill point fastener with #3 Phillips head.	Various Lengths	Duro-Last Roofing, Inc.
9.	Duro-Last Fluted Concrete Nails	Corrosion resistant, 0.22" shank with a flat top pan head.	Various Lengths	Duro-Last Roofing, Inc.
10.	Trufast #12 Purlin Fastener	Carbon steel screw with #3 square drive, modified truss head and long pilot-point for use in min. 18 ga. steel purlin. TruKote epoxy coating.	#12 x 8-3/4" max. length	Altenloh, Brinck & Co. U.S., Inc.
11.	Duro-Last #14 HD Fasteners	Roofing and insulation fasteners, Duro-Coated with #3 Phillips head.	Various	Duro-Last Roofing, Inc.
12.	Duro-Last Cleat Plates	0.035" thick galvalume stress plate	2-3/8"	Duro-Last Roofing, Inc.
13.	OMG XHD	Carbon steel fastener with #3 phillips head	Various lengths	OMG, Inc.
14.	Trufast DP #12 Fasteners	Carbon steel screw with #3 Phillips drive	#12 x 8" max. length	Altenloh, Brinck & Co. U.S., Inc.
15.	Duro-Bond Plate 1302	Round, coated galvalume plate (Gold and Black)	3" round	Duro-Last Roofing, Inc.
16.	OMG Eyehook Accuseam Plate	• '	2-3/8"	OMG, Inc.
17.	Trufast Twin Loc-Nail Assembled Fastener	Three-piece preassembled fastener/plate unit	2.7" plate x 4.8" max. length	Altenloh, Brinck & Co. U.S., Inc.
18.	Duro-Last Auger Plates	2" metal plate for use Duro- Last Auger Fastener	2" round	Duro-Last Roofing, Inc.



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 5 of 111

APPROVED FASTENERS:

TABLE 3


Fastener Number	Product Name	Product Description	Dimensions	Manufacturer (With Current NOA)
19.	Duro-Last Auger Fastener	Glass-filled nylon fastener for use with Duro-Last Auger Plates	Various lengths	Duro-Last Roofing, Inc.
20.	Duro-Last Duro-Auger	Composite nylon and fiberglass fastener/plate system with epoxy injection	Various Lengths	Duro-Last Roofing, Inc.
21.	OMG XHD	Carbon steel fastener with #3 phillips head	Various lengths	OMG, Inc.
22.	Trufast Twin Loc Coiled Batten Bar	Batten bar for mechanical attachment of membrane	1" wide 0.040" wide 100' length	Altenloh, Brinck & Co. U.S., Inc.
23.	Trufast Twin Loc Nail Batten Fastener	Two-piece assembled fastener. AZ-55 Galvalume or G-90 and stainless steel or coated steel fastener	Various lengths	Altenloh, Brinck & Co. U.S., Inc.
24.	Dekfast #12 Purlin Fasteners	#3 Sq. Drive, drill point fastener for steel purlins	Various	SFS Intech, Inc.
25.	Isoweld F1-P-6.8-PVC Plate	G-90 steel plate with PVC coating for insulation	3" dia.	SFS Intech, Inc.
26.	Millennium One Step Foamable Adhesive	Dual component, low-rise polyurethane foam adhesive.	1.5 liter 4 cartridges per case	Adco Products, Inc. dba Royal Adhesives & Sealants
27.	Insta Stik Quik Set Insulation Adhesive	Single component polyurethane adhesive	30 lb. steel tank	The Dow Chemical Company
28.	OMG Olybond 500	Dual component, low-rise polyurethane foam adhesive.	10 gallon Bag- in-Box sets or 1.5 liter l cartridges	OMG, Inc.



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 6 of 111

EVIDENCE SUBMITTED:

Test Agency/Identifier	<u>Name</u>	Report	Date
Architectural Testing, Inc.	C0713.01-109-18	TAS 114(J)	03/05/13
Factory Mutual Research Corp.	J.I. 3Y5A6.AM	FM 4470	03/10/95
	J.I. 2M4A8 .AM	FM 4470	03/05/87
	J.I. 3Y5A6.AM	FM 4470	03/10/95
	J.I. 1X2A7 .AM	FM 4470	09/17/93
	J.I 1X8A8.AM	FM 4470	11/01/93
	AD6A4.AM	FM 4470	08/09/99
	3005604	FM 4470	03/13/00
	3008342	FM 4470	10/19/00
	3026508	FM 4470	05/03/07
	3015816	FM 4470	01/09/03
	3010289	FM 4470	04/13/01
	3040346	FM 4470	09/28/11
	3040741	FM 4470	12/02/11
	3028306	FM 4470	08/03/09
	3037919	FM 4470	05/12/10
	3023458	FM 4470	07/18/06
	3012321	FM 4470	07/29/02
	3032172	FM 4470	06/12/09
	3010987	FM 4470	04/23/02
	3047477	FM 4470	10/03/12
	3006989	FM 4470	02/09/01
	3014929	FM 4470	05/23/03
	3014692	FM 4470	08/05/03
	3044466	FM 4470	11/07/12
	3055227	FM 4470	05/21/15
Exterior Research & Design, LLC	#02733.01.05-1	TAS 114	01/21/05
	#02744.05.06	TAS 114	05/17/06
	02732.09.04	ASTM D4434	09/28/04
	02742.10.05	TAS 117(A) & (B)	10/12/05
	0237.03.05.01	TAS 114	03/21/05
	02745.08.06	TAS 117(A)	08/04/06
Trinity ERD	02750.02.08-R2	ASTM D4434	08/03/12
	D42370.07.12	ASTM D1084 / TAS 117	07/11/12
	D35210.08.11-R1	ASTM D4434	09/17/12
	D6760.08.07	TAS 114	08/01/07
	C8500SC.11.07	TAS 117(B)	11/30/07
	D35210.08.11-R3	ASTM D4434	03/29/13
	D40260.03.13-1	ASTM D4434	03/29/13
	D40280.03.13	ASTM D4434	03/13/13
	D41660.11.12-R2	TAS 114(D & J)	03/25/13
	D42320.08.12	TAS 114(J)/TAS 117(A)	08/21/12
	D42390.10.12-R1	TAS 114(J)	10/03/12
	D43030.1.13-R1	TAS 114(J)/TAS 117(A)	10/02/13
	SC10010.02.16	TAS 114 J	02/29/16





EVIDENCE SUBMITTED: (Continued)

Test Agency/Identifier	<u>Name</u>	<u>Report</u>	Date
Trinity ERD	D44450.05.13-2	ASTM D4434	05/10/13
- 1	02733.01.05-1	TAS 114(J)	01/21/05
Intertek Testing Services, NA Inc.	3119586-001	TAS 111	07/10/07
PRI Construction Materials	DLRI-013-02-01	TAS 114(J)	08/28/12
Technologies, LLC	DLRI-014-02-01	TAS 114(J)	08/28/12
	DLRI-021-02-01.12 2	ASTM D1876/D1761	06/27/17
		TAS 117(A)/(B)	
		TAS 114(D)	
	DLRI-029-02-01	TAS 114(J)	10/25/12
	DLRI-030-02-01	TAS 114(D)	04/01/13
	DLRI-041-02-01	TAS 114(J)	09/17/13
	DLRI-045-02-01	TAS 114(D)	08/24/13
	DLRI-045-02-02	TAS 114(D)	09/13/13
	DLRI-046-02-01	TAS 114(J)	08/24/13
	DLRI-047-02-01	TAS 114(J)	08/24/13
	DLRI-068-02-01.1	TAS 114(D)	07/28/14
	DLRI-070-02-01	TAS 114(J)	07/30/14
	DLRI-073-02-01.1	TAS 114(J)	04/23/15
	DLRI-073-02-02	TAS 114(J)	11/18/14
	DLRI-077-02-01	TAS 114 (D)	04/07/15
	DLRI-079-02-01.1	TAS 114(J)	08/08/17
	DLRI-086-02-01	TAS 114(J)	10/07/15
	DLRI-086-02-02	TAS 114(J)	09/18/15
	DLRI-096-02-01.1	TAS 114(J)	08/28/17
	DLRI-090-02-01	TAS 114(J)	02/01/16
	DLRI-099-02-01	FM 4474 D & TAS 114 (J)	07/20/16
	DLRI-100-02-01	TAS 114(J)	06/07/17
	DLRI-115-02-01	TAS 114 (J)	04/05/17
UL LLC	R10128	UL790	03/31/15
	R11183	UL723	11/19/09
RADCO	RAD-5135	ASTM C578	05/02/12

DECK STRESS ANALYSIS CALCULATIONS/REPORTS

Engineer/Agency	<u>Identifier</u>	<u>Assemblies</u>	Date
FM Approval Deck Limitations	N/A	C(1), C(3), C(4), C(31), D(2), D(3), D(4), D(11), D(12), D(13), D(14), D(15), D(16), D(19), D(30), D(42)	01/01/13
Zachary R. Priest, P.E.	Signed/Sealed Calculations	E(12), E(13), E(14) C(5), C(7), C(9), C(11), C(13), C(15), C(17), C(28), C(29), C(30), D(5), D(17), D(18), D(24), D(25), D(26), D(27), D(28), D(29), E(1), E(5), E(7), E(16) E(11), E(18) D(31), D(32), D(33), D(34), D(35), D(36) E(17)	10/07/15 02/18/16 02/18/16 02/19/16 02/19/16 02/19/16 06/07/16 07/24/17 08/08/17

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 8 of 111



APPROVED ASSEMBLIES:

Membrane Type: Single Ply, PVC

Deck Type 7I: Recover, Insulated

Deck Description: 18-22 ga. Steel

System Type A(1): All layers of insulation fully adhered with approved adhesive; membrane fully

adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft ²
SECUROCK Gypsum-Fiber Roof Board, DensDeck		-
Maximum 1" thick	N/A	N/A

Note: Layers of insulation shall be adhered to substrate with Duro-Fleece Membrane Adhesive applied in continuous ¾ in. wide ribbons spaced 6 in. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum

1.5" wide heat

Or

Duro-Tuff, Duro-last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a

minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at 140 ft²/gal. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: –45 psf. (See General Limitation #9)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 9 of 111 **Membrane Type:** Single Ply, PVC

Deck Type 7I: Recover, Insulated

Deck Description: Concrete

System Type A(2): One or more layers of insulation adhered with approved adhesive over existing

asphaltic BUR; membrane fully adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer Insulation Fasteners Fastener
(Table 3) Density/ft²
AC Foam II, H-Shield, Duro-Guard Iso II-H, Duro-Guard Iso II-A, Duro-Guard Iso II-G

Minimum 1.5" thick

N/A

N/A

N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Pensity/ft²

ACFoam II, Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-G,

Duro-Guard Iso II-H, Duro-Guard Iso III-H, Duro-Guard EPS

Minimum 1/2" thick N/A N/A

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board

Minimum 1/4" thick N/A N/A

Duro-Guard Iso HD-A, Duro-Guard Iso HD-G, Duro-Guard Iso HD- H

Minimum 1/2" thick N/A N/A

Note: Layers of insulation shall be adhered with OlyBond 500 applied in $\frac{3}{4}$ " – 1" ribbons spaced 12-inch. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum

1.5" wide heat

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a

minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at 140 ft²/gal. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -112.5 psf. (See General Limitation #9)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 10 of 111

Deck Description: Concrete

System Type A(3): One or more layers of insulation adhered with approved adhesive over existing

asphaltic BUR; membrane fully adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft ²
Multi-Max FA-3, ACFoam III, Duro-Guard Iso III-A,	ISO 95+ GL	
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners	Fastener
ı v	(Table 3)	Density/ft ²
SECUROCK Gypsum-Fiber Roof Board		

Note: Layers of insulation shall be adhered with TITESET Roofing Adhesive applied in a continuous 1.5-inch wide ribbon in rows spaced 12-inch. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

N/A

N/A

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum

1.5" wide heat

Or

Duro-Tuff, Duro-last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a

minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at $140~\rm{ft^2/gal}$. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Minimum ¼" thick

Pressure: -240 psf. (See General Limitation #9)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 11 of 111

Deck Description: Concrete

System Type A(4): One or more layers of insulation adhered with approved adhesive over existing

asphaltic BUR; membrane fully adhered with approved adhesive.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
ACFoam II, Duro-Guard Iso II-A Minimum 2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners	Fastener
•	(Table 3)	Density/ft ²
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	N/A	N/A

Note: Layers of insulation shall be adhered with TITESET Roofing Adhesive applied in continuous 3 to $3\frac{1}{2}$ inch wide ribbon in rows spaced 12-inch. o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum

1.5" wide heat

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a

minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at $140~\rm{ft^2/gal}$. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: –247.5 psf. (See General Limitation #9)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 12 of 111

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5 fasteners

to supports having a maximum spacing of 6' o.c. Side laps secured with Traxx 1

fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(1): All layers of insulation simultaneously attached, membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations not to exceed 1" max.

Insulation Layer	Insulation Fasteners	Fastener
·	(Table 3)	Density/ft ²
SECUROCK Gypsum-Fiber Roof Board, DensDeck Prime		
Maximum 1" thick	11 with 1	1:1.33 ft ²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum 1.5"

wide heat weld.

Or

Duro-Tuff, Duro-Last EV membrane or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with

a minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV membrane or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at 140 ft²/gal. Laps are sealed with a minimum

1.5" wide heat weld.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 13 of 111 **Membrane Type:** Single Ply, PVC

Deck Type 7I: Recover, Insulated

Deck Description: Concrete deck.

System Type C(2): All layers of insulation simultaneously attached, membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners	Fastener
•	(Table 3)	Density/ft ²
SECUROCK Gypsum-Fiber Roof Board		
Minimum 1/4" thick	11 with 1	1:1.33 ft ²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs /100 ft² in "splotter" pattern. Long are spaled with a minimum

20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum

1.5" wide heat

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a

minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at 140 ft²/gal. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 14 of 111 **Membrane Type:** Single Ply, PVC

Deck Type 7I: Recover, Insulated

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5 fasteners

to supports having a maximum spacing of 6' o.c. Side laps secured with Traxx 1

fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(3): All layers of insulation simultaneously attached, membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations not to exceed 1" max.

Insulation Layer Insulation Fasteners (Table 3) Density/ft²

DensDeck Prime

Maximum_1" thick 7 with 1 1:1.6 ft²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing

Application Standard RAS 117 for fastening details.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum 1.5"

wide heat

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a minimum

1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at 140 ft²/gal. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 15 of 111

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5 fasteners

to supports having a maximum spacing of 6' o.c. Side laps secured with Traxx 1

fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(4): All layers of insulation simultaneously attached, membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations not to exceed 1" max...

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft ²
DensDeck Prime		
Maximum 1" thick	11 with 1	1:1.33 ft ²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20 applied at 8 lbs./100-ft² in "splatter" pattern. Laps are sealed with a minimum

1.5" wide heat

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60ft²/gal total coverage. Laps are sealed with a

minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV or Duro-Last membrane fully adhered with Duro-Last WB II Adhesive applied at $140~\rm{ft^2/gal}$. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: –67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 16 of 111

Deck Description: Min. 18 ga., Grade 33 steel deck with supports spaced maximum 6 ft. o.c. The

deck should record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(5): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H. Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel deck</u> with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded

to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -90 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 17 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly). The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(6): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, , Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Insulation Layer shall be through fastened to the steel purlins with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel purlins

at maximum 6" o.c. in rows spaced a maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a

minimum 1.5" wide heat weld.

Maximum Design

Pressure: -90 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 18 of 111

Deck Description: Min. 18 ga., Grade 33 steel deck with supports spaced maximum 6 ft. o.c. The

deck should record a Minimum Characteristic Resistance Force (MCRF) of 315 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(7): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel deck</u> with the fastener and

plate listed above. The Duro-Last, Duro-Last EV or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and spacing specified

below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 72" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 19 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly). The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 315 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(8): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Insulation Layer shall be through fastened to the steel purlin with the fastener

and plate listed above. The Duro-Last, Duro-Last EV or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and spacing

specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel

purlins at maximum 6" o.c. in rows spaced a maximum of 72" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed

with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 20 of 111

Deck Description: Min. 18 ga., Grade 33 steel deck with supports spaced maximum 6 ft. o.c. The

deck should record a Minimum Characteristic Resistance Force (MCRF) of 420 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(9): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel deck</u> with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 96" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 21 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly). The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 420 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(10): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Insulation Layer shall be through fastened to the steel purlin with the fastener and

plate listed above. The Duro-Last membrane (0.057" min, Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min)) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel purlins

at maximum 6" o.c. in rows spaced a maximum of 96" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a

minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 22 of 111

Deck Description: Min. 18 ga., Grade 33 Type B steel with supports spaced maximum 6 ft. o.c.

The deck should record a Minimum Characteristic Resistance Force (MCRF) of 413 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(11): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners (Table 3)

Fastener Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-Guard Iso II H

Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel deck</u> with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded

to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 60" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 23 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly). The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 413 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(12): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel purlins</u> with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel purlins

at 6" o.c. in rows spaced a maximum of 60" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum

1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 24 of 111

Deck Description: Min. 18 ga., Grade 33 steel deck with supports spaced maximum 6 ft. o.c. The

deck should record a Minimum Characteristic Resistance Force (MCRF) of 330 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(13): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H. Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel deck</u> with the fastener and

plate listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and

spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 25 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly). The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 330 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(14): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick $\frac{N}{A}$

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Insulation Layer shall be through fastened to the steel purlins with the fastener

and plate listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and

spacing specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel

purlins at maximum 6" o.c. in rows spaced a maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed

with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 26 of 111

Deck Description: Min. 18 ga., Grade 33 steel deck with supports spaced maximum 6 ft. o.c. The

deck should record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(15): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

 $\begin{array}{ccc} Base\ Insulation\ Layer\ (Optional) & Insulation\ Fasteners & Fastener \\ & (Table\ 3) & Density/ft^2 \end{array}$

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel deck with the fastener and</u>

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 12" o.c. in rows spaced a

maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 27 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly). The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(16): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $\frac{1}{2}$ " thick $\frac{N}{A}$

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel purlins</u> with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded

to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel purlins

at maximum 12" o.c. in rows spaced a maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a

minimum 1.5" wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 28 of 111

Deck Description: Min. 18 ga., Grade 33 steel deck with supports spaced maximum 6 ft. o.c. The

deck should record a Minimum Characteristic Resistance Force (MCRF) of 450 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(17): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

 $\begin{array}{ccc} Base\ Insulation\ Layer\ (Optional) & Insulation\ Fasteners & Fastener \\ & (Table\ 3) & Density/ft^2 \end{array}$

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 7 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 7 with 15 See below

DensDeck Prime

Minimum 0.25" thick 7 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Insulation Layer shall be through fastened to the steel deck with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 120" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 29 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly) The steel

purlin should record a Minimum Characteristic Resistance Force (MCRF) of 450 lbf when tested with Trufast #12 Purlin Fastener installed through to the

purlin in accordance with TAS 105.

System Type C(18): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 10 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 10 with 15 See below

DensDeck Prime

Minimum 0.25" thick 10 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: <u>Insulation Layer shall be through fastened to the steel purlins</u> with the fastener and

plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached through to minimum 16 ga. steel purlins

at maximum 6" o.c. in rows spaced a maximum of 120" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a

minimum 1.5" wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 30 of 111

Deck Description: Min. 2500 psi concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 225 lbf when tested with Duro-Last #14 HD Fasteners installed through to the deck in accordance with TAS 105.

System Type C(19): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 See below

DensDeck Prime

Minimum 0.25" thick 11 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Insulation Layer shall be through fastened to the concrete deck with the fastener

and plate listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and

spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 60" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 31 of 111

Deck Description: Min. 2500 psi concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 210 lbf when tested with Duro-Last #14 HD Fasteners installed through to the deck in accordance with TAS 105.

System Type C(20): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, , Duro-Guard Iso II-H,

Duro-Guard Iso III-H. Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 See below

DensDeck Prime

Minimum 0.25" thick 11 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Insulation Layer shall be through fastened to the concrete deck with the fastener

and plate listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and

spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 32 of 111

Deck Description: Min. 2500 psi concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 280 lbf when tested with Duro-Last #14 HD Fasteners installed through to the deck in accordance with TAS 105.

System Type C(21): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Any Approved EPS or XPS listed in Table 2, D	,	•
Guard Iso II-H		,
Minimum ¹ / ₂ " thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Duro-Guard Iso II-A, Duro-Guard Iso III-A, I	Ouro-Guard Iso II-H,	v
Duro-Guard Iso III-H, Duro-Guard Iso II-G	,	
Minimum 1.5" thick	11 with 15	1:2.67 ft ²
SECUROCK Gypsum-Fiber Roof Board, Duro	-Guard Iso HD-G	
Minimum 0.5" thick	11 with 15	1:2.67 ft ²
DensDeck Prime		
Minimum 0.25" thick	11 with 15	1:2.67 ft ²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: <u>Insulation Layer shall be through fastened to the concrete deck</u> with the fastener

and plate and density listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the

manner and spacing specified below.

Fastening: Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder.

Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Ptressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 33 of 111

Deck Description: Min. 2500 psi concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 210 lbf when tested with Duro-Last #14 HD Fasteners installed through to the deck in accordance with TAS 105.

System Type C(22): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Any Approved EPS or XPS listed in Table 2, Dui	,	•
Guard Iso II-H	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	11 0, 2 11 0
Minimum ¹ / ₂ " thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-	ro-Guard Iso II-H,	·
Duro-Guard Iso III-H, Duro-Guard Iso II-G	,	
Minimum 1.5" thick	11 with 15	$1:2.0 \text{ ft}^2$
SECUROCK Gypsum-Fiber Roof Board, Duro-G	Guard Iso HD-G	
Minimum 0.5" thick	11 with 15	$1:2.0 \text{ ft}^2$
DensDeck Prime		
Minimum 0.25" thick	11 with 15	$1:2.0 \text{ ft}^2$

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: <u>Insulation Layer shall be through fastened to the concrete deck</u> with the fastener

and plate and density listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing

specified below.

Fastening: Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder.

Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 34 of 111

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 12-inches o.c. in the field. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 420 lbf when tested with

Duro-Last #14 HD Fasteners installed through to the wood support in

accordance with TAS 105.

System Type C(23): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10[®]Fire Retardant Slip Sheet, ¹/₄" DensDeck, or

(Optional) ¼" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 See below

DensDeck Prime

Minimum 0.25" thick 11 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Insulation Layer shall be through **fastened into the wood supports** with the

fastener and plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified below.

Fastening: Insulation shall be mechanically attached at maximum 12" o.c. in rows spaced a

maximum of 48" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 35 of 111

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 12-inches o.c. in the field. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 320 lbf when tested with

Duro-Last #14 HD Fasteners installed through to the wood support in

accordance with TAS 105.

System Type C(24): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10[®]Fire Retardant Slip Sheet, ¹/₄" DensDeck, or

(Optional) ¼" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners (Table 3)

Fastener Density/ft²

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 1:2.67

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 1:2.67

DensDeck Prime

Minimum 0.25" thick 11 with 15 1:2.67

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Insulation Layer shall be through fastened into the wood supports with the

fastener and plate listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the

manner and spacing specified below.

Fastening: Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder.

Laps are sealed with a minimum 1" wide heat weld.

Maximum Design

Pressure: -60 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 36 of 111

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 12-inches o.c. in the field. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 480 lbf when tested with

Duro-Last #14 HD Fasteners installed through to the wood support in

accordance with TAS 105.

System Type C(25): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼" DensDeck, or

(Optional) ½" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 See below

DensDeck Prime

Minimum 0.25" thick 11 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Insulation Layer shall be through fastened into the wood supports with the

fastener and plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified

below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 96" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1" wide heat weld.

Maximum Design

Pressure: -60 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 37 of 111

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 12-inches o.c. in the field. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf when tested with

Duro-Last #14 HD Fasteners installed through to the wood support in

accordance with TAS 105.

System Type C(26): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼" DensDeck, or

(Optional) ¼" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener

Density

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum $^{1}\!/_{2}$ " thick N/A N/A
Top Insulation Layer Insulation Fasteners (Table 3) Fensity

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 See below

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 See below

DensDeck Prime

Minimum 0.25" thick 11 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Insulation Layer shall be through fastened into the wood supports with the

fastener and plate listed above. The Duro-Last membrane (0.057" min), Duro-Tuff (.080" min) membrane or Duro-Last EV membrane (.060" min) shall be induction welded to Duro-Bond Plates in the manner and spacing specified

below.

Fastening: Insulation shall be mechanically attached at maximum 6" o.c. in rows spaced a

maximum of 72" o.c. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps are sealed with a minimum 1" wide heat weld.

Maximum Design

Pressure: -60 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 38 of 111

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 12-inches o.c. in the field. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 360 lbf when tested with

Duro-Last #14 HD Fasteners installed through to the wood support in

accordance with TAS 105.

System Type C(27): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼" DensDeck, or

(Optional) ¼" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Density

Any Approved EDS on VDS listed in Table 2. Dura Guard Iso H.A. Dura Guard Iso H.C. Dura

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-Guard Iso II-H

Minimum $\frac{1}{2}$ " thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1.5" thick 11 with 15 1:2

SECUROCK Gypsum-Fiber Roof Board, Duro-Guard Iso HD-G

Minimum 0.5" thick 11 with 15 1:2

DensDeck Prime

Minimum 0.25" thick 11 with 15 1:2

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: <u>Insulation Layer shall be through fastened into the wood supports</u> with the fastener

and plate listed above. The Duro-Last, Duro-Last EV membrane or Duro-Tuff membrane shall be induction welded to Duro-Bond Plates in the manner and

spacing specified below.

Fastening: Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder. Laps

are sealed with a minimum 1" wide heat weld.

Maximum Design

Pressure: -90 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 39 of 111

Deck Description: Minimum 22 ga., Grade 33 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 420 lbf when tested with OMG XHD installed through to the

deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(28): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft2

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Pensity/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H. Duro-Guard Iso II-G

Minimum 1" thick 13 with 15 See below

Duro-Guard Iso HD-A, Duro-Guard Iso HD-G, Duro-Guard Iso HD-H

Minimum 0.5" thick 13 with 15 See below

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board

Minimum 0.25" thick 13 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Duro-Last, Duro-Last EV membrane or Duro-Tuff Membrane with shall be

induction welded to Duro-Bond Plates 1302 in the manner and spacing specified

below.

Fastening: Insulation shall be mechanically attached maximum 24-inch o.c. in rows spaced

maximum 24-inch o.c. Two rows are installed in a non-staggered pattern and two rows are staggered 12- inches. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond welder. Minimum 1-inch wide weld at lap seams.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 40 of 111

Deck Description: Minimum 22 ga., Grade 33 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 450 lbf when tested with OMG XHD installed through to the

deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(29): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft2

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Pensity/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1" thick 13 with 15 See below

Duro-Guard Iso HD-A, Duro-Guard Iso HD-G, Duro-Guard Iso HD-H

Minimum 0.5" thick 13 with 15 See below

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board

Minimum 0.25" thick 13 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Duro-Last, Duro-Last EV membrane or Duro-Tuff shall be induction welded to

Duro-Bond Plates 1302 ithe manner and spacing specified below.

Fastening: Insulation shall be mechanically attached maximum 24-inch o.c. in rows spaced

maximum 18-inch o.c. Two rows are installed in a non-staggered pattern and two rows are staggered 12- inches. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond welder. Minimum 1-inch wide weld at lap seams.

Maximum Design

Pressure: -75 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 41 of 111

Deck Description: Minimum 22 ga., Grade 33 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 540 lbf when tested with OMG XHD fastener installed

through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type C(30): All layers of insulation simultaneously attached. Membrane adhered to plates.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft2

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso II-G, Duro-

Guard Iso II-H

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum 1" thick 13 with 15 See below

Duro-Guard Iso HD-A, Duro-Guard Iso HD-G, Duro-Guard Iso HD-H

Minimum 0.5" thick 13 with 15 See below

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board

Minimum 0.25" thick 13 with 15 See below

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Membrane: Duro-Last, Duro-Last EV membrane or Duro-Tuff Membrane with shall be

induction welded to Duro-Bond Plates 1302 in the manner and spacing specified

below.

Fastening: Insulation shall be mechanically attached maximum 24-inch o.c. in rows spaced

maximum 36-inch o.c. Two rows are installed in a non-staggered pattern and two rows are staggered 12- inches. Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond welder. Minimum 1-inch wide heat weld at lap

seams.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 42 of 111

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5

fasteners to supports having a maximum spacing of 6' o.c. Side laps secured with

Traxx 1 fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted

System Type C(31): All layers of insulation simultaneously attached, membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations not to exceed 1" max.

Insulation Layer Insulation Fasteners (Table 3) Fastener SECUROCK Gypsum-Fiber Roof Board, DensDeck Prime Maximum 1-2" thick 14 with 1 1:1 ft²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Duro-Fleece or Duro-Fleece Plus membrane fully adhered with Duro-Last WB II

Adhesive applied at 100 ft²/gal. Laps are sealed with a minimum 1.5" wide heat

weld. Or

Duro-Tuff ,Duro-Last EV membrane or Duro-Last membrane fully adhered with Duro-Last SB IV Adhesive applied at 60 ft²/gal total coverage. Laps are sealed

with a minimum 1.5" wide heat weld.

Or

Duro-Tuff, Duro-Last EV membrane or Duro-Last membrane fully adhered with

Duro-Last WB II Adhesive applied at 140 ft²/gal. Laps are sealed with a

minimum 1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 43 of 111

Deck Description: Steel (Existing Structural Non-Insulated Metal Roof Panel Assembly).

System Type D(1): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer: (To be placed between the ribs Insulation Fasteners or over panels of existing structural metal roof system.) (Table 3) Density/ft2 ACFoam II, ACFoam III, Duro-Guard Iso II-A, Duro-Guard Iso III-A, ENRGY-3, ISO 95+ GL, Ultra-Max, Duro-Guard Iso II-G

Minimum 1.5" thick N/A N/A

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS, Kingspan GreenGuard Insulation Board CM

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener

(Table 3) Density/ft²

ACFoam II, ACFoam III, Duro-Guard Iso II-A, Duro-Guard Iso III-A, ENRGY-3, ISO 95+ GL, Ultra-Max, Kingspan GreenGuard Insulation Board CM, Duro-Guard ISO II-H

Minimum 1" thick N/A N/A

Duro-Guard Iso HD-G, DensDeck, DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, DEXcell FA Glass Mat Roof Board

Minimim 0.25" thick N/A N/A

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane with 60" tabs: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 60" o.c. with Tru-Fast Purlin Fasteners with Duro-Last Poly-plates or Duro-Last Cleat Plates spaced 12" o.c. maximum, through the insulation and through the deck into the purlins spaced 5' o.c. Laps are

sealed with a minimum 1.5 in. heat weld.

(Maximum Design Pressure -45 psf. See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 44 of 111 Membrane with 72" tabs: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 72" o.c. with Tru-Fast Purlin Fasteners with Duro-Last Poly-plates or Duro-Last Cleat Plates spaced 6" o.c. maximum, through the insulation and through the deck into the purlins spaced 6' o.c. Laps are

sealed with a minimum 1.5 in. heat weld.

(Maximum Design Pressure -52.5 psf. See General Limitation #7)

Membrane with 120" tabs: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 120" o.c. with Tru-Fast Purlin Fasteners Duro-Last Polyplates or Duro-Last Cleat Plates spaced 6" o.c. maximum, through the insulation and through the deck into the purlins spaced 5' o.c. Laps are

sealed with a minimum 1.5 in. heat weld.

(Maximum Design Pressure -52.5 psf. See General Limitation #7)

Maximum Design

Pressure: See Fastening Requirements above.



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 45 of 111

Deck Description: Structural Concrete or minimum 22 gauge, type B, Grade 80 steel deck attached

to supports having a maximum span of 6 ft. o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports with washers. Deck side laps secured maximum 24" o.c. with

Traxx/1 fasteners.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(2): All layers of insulation are preliminarily attached to roof deck as specified below.

Membrane is mechanically attached to deck through the insulation layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft ²
AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3	25 PSI, Duro-Guard Iso II	I-G,
Duro-Guard II-H, Duro-Guard HD-G		
Minimum 1½" thick	3 with 6	1:4 ft ²
	3 with 6	1:6.4 ft ²
Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Ins	ulfoam EPS	
Minimum ½" thick	3 with 6	1:4 ft ²
	3 with 6	1:6.4 ft ²
Kingspan GreenGuard Insulation Board CM		
Minimum 1" thick	3 with 6	1:4 ft ²
	3 with 6	$1:6.4 \text{ ft}^2$

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼"

DensDeck, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core, or a second sheet of barrier board may be used over the insulation

(see General Limitation #1).

Membrane, 60" tabs: (Steel or Concrete only) Duro-Last membrane shall be mechanically attached at

its minimum 3" tabs, spaced maximum 60" o.c. with Duro-Last fasteners and Duro-Last Poly-plates or Duro-Last Cleat Plates, or Duro-Last Fluted Concrete Nails (for structural concrete only) spaced 12" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat

weld.

(Maximum Design Pressure -45 psf. See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 46 of 111

(Steel only) Duro-Last membrane shall be mechanically attached at its minimum Membrane, 27" tabs:

3" tabs, spaced maximum 27" o.c. with Duro-Last fasteners and Duro-Last Polyplates or Duro-Last Cleat Plates spaced 18" o.c. maximum, through the insulation

and into the deck. Laps are sealed with a minimum 1.5" wide heat weld. (Maximum Design Pressure -45 psf. See General Limitation #7)

Membrane, 28" tabs: (Concrete only) Duro-Last membrane shall be mechanically attached at its

> minimum 3" tabs, spaced maximum 28" o.c. with Duro-Last Fluted Concrete Nails, Duro-Last #14 HD Fastener, Duro-Last #14 Concrete Screws and Duro-Last Poly-plates or Duro-Last Cleat Plates spaced 6" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat

(Maximum Design Pressure -105 psf. See General Limitation #7)

Membrane, 28" tabs: (Steel only) Duro-Last[®] membrane shall be mechanically attached at its minimum

3" tabs, spaced maximum 28" o.c. with Duro-Last fasteners with Duro-Last Polyplates or Duro-Last Cleat Plates spaced at 6" o.c. maximum, through the

insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat

(Maximum Design Pressure -105 psf. See General Limitation #7)

Maximum Design

See Fastening Requirements above. Pressure:



NOA No.: 17-0202.08 **Expiration Date: 08/22/22** Approval Date: 10/19/17

Page 47 of 111

Deck Type 7I: Recover, Insulated

Deck Description: 1. Structural Concrete

- 2. Minimum 22 gauge, type B, Grade 80 steel deck attached to supports having a maximum span of 54 in. o.c.
- 3. Minimum 20 gauge, type B, Grade 80 steel deck attached to supports having a maximum span of 72 in. o.c

Steel deck options listed above shall be fastened with Traxx/5 fasteners spaced 6" o.c. at the supports with washers. Deck side laps secured maximum 24" o.c. with Traxx/1 fasteners.

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submitted Table.

System Type D(3): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of following:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
ACFoam II, Duro-Guard Iso II-A, ACFoam III Duro-Guard Iso II-G, Duro-Guard II-H, Duro-	, Duro-Guard Iso III-A, ENRGY-3, I	•
Minimum 1½" thick	N/A	N/A
Cellofoam Type IX EPS Insulation, Duro-Guard	d EPS, Insulfoam EPS	
Minimum ½" thick	N/A	N/A
Kingspan GreenGuard Insulation Board CM		
Minimum 1" thick	N/A	N/A
DEXcell FA Glass Mat Roof Board, SECUROC	K Gypsum Fiber Roof Board	
Minimum ¼" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 120" with Duro-Last Poly-plates or Duro-Last Cleat Plates and Duro-Last #14 HD Fasteners or Fluted Nail (concrete) spaced 6" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -52.5 psf. . (See Genetal Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 48 of 111

Deck Description: Stuctural Concrete or Minimum 22 gage, Type B, Grade 80 steel deck attached

with ITW Buildex Traxx/4 or Traxx/5 fastener at a maximum spacing of 6" o.c., to minimum 1/4" thick steel supports having a maximum span of 6 ft. o.c. Sidelaps

are attached with Traxx/1 fasteners at 30" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(4): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One of more layers of the following:

Insulation Layer	Insulation Fasteners	Fastener Density/ft ²
	(Table 3)	
ACFoam II, Duro-Guard Iso II-A, ACFoam III	I, Duro-Guard Iso III-A, Duro-Guard	l Iso II-G,
Duro-Guard II-H, Duro-Guard HD-G		
Minimum 1½" thick	N/A	N/A
Cellofoam Type IX EPS Insulation, Duro-Guar	d EPS, Insulfoam EPS	
Minimum ½" thick	N/A	N/A
Kingspan GreenGuard Insulation Board CM		
Minimum 1" thick	N/A	N/A
DEXcell FA Glass Mat Roof Board, SECUROC	CK Gypsum Fiber Roof Board	
Minimum 1/4" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: Top layer shall have preliminary attachment, prior to the installation of the base/anchor sheet, at a minimum application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. All layers of insulation and base sheet shall be simultaneously fastened. See base/anchor sheet below for fasteners and density.

Membrane: Duro-Last membrane shall be mechanically attached as described below:

Fastener #1: Membrane shall be fastened at its minimum 3" tabs, spaced maximum 28" o.c.

with Duro-Last #14 HD Fasteners and Duro-Last Poly-plates or Duro-Last Cleat

Plates or Duro-Last 3" Metal Insulation Plates, Or OMG Fluted Concrete Nails

(concrete only), spaced 18" o.c. maximum, through the insulation and into the

deck. Laps are sealed with a minimum 1.5" wide heat weld.

(Maximum Design Pressure -52.5 psf. See General Limitation #7)

Fastener #2: Membrane shall be fastened at its minimum 3" tabs, spaced maximum 28" o.c. with Duro-Last #14 HD Fasteners and Duro-Last Poly-plates or Duro-Last Cleat

Plates or Duro-Last 3" Metal Insulation Plates, Or OMG Fluted Concrete Nails (concrete only) spaced 6" o.c. through the insulation and into the deck. Laps are

sealed with a minimum 1.5" wide heat weld.

(Maximum Design Pressure -105 psf. See General Limitation #7)

Maximum Design

Pressure: See Fastening Requirements above.



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 49 of 111

Deck Description: Minimum 22 gauge, Type B, Grade 80 steel attached to steel supports spaced 5-

ft. o.c. The deck should record a Minimum Characteristic Resistance Force

(MCRF) of 338 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point

Fastener installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(5): Insulation is preliminarily attached to roof deck as specified below. Membrane

is mechanically attached to deck through the insulation layer.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft ²
ACFoam II, Duro-Guard Iso II-A, ACFoam III, Duro-Guard Iso II-A, ACFoam III-A, ACFoam III	ard Iso III-A, Duro-Guard	Iso II-G,
Duro-Guard II-H, Duro-Guard HD-G		
Minimum 1½" thick	7, 2	1:6.4 ft ²
SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type	IX EPS Insulation, Duro-	Guard EPS,
Insulfoam EPS		
Minimum ½" thick	7, 2	1:6.4 ft ²
Kingspan GreenGuard Insulation Board CM		
Minimum 1" thick	7, 2	1:6.4 ft ²

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" wide tabs,

spaced maximum 60" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners with Duro-Last Batten Bar 6" o.c. maximum, through the insulation and into the deck. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal (two-sided

application). Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 50 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Concrete

System Type D(6): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Insulation Layer Insulation Fasteners (Table 3) Density/ft²

ACFoam II, Duro-Guard Iso II-A, ACFoam III, Duro-Guard Iso III-A, ENRGY-3, ISO 95+ GL,

Multi-Max FA-3, Duro-Guard Iso II-G, Duro-Guard II-H, Duro-Guard HD-G, Kingspan

GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, DEXcell FA Glass Mat Roof Board

Minimum 0.25" thick N/A N/A

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" wide tabs,

spaced maximum 120" o.c. with Duro-Last Poly-plates or Duro-Last Cleat Plates and Duro-Last #14 HD Fasteners or Duro-Last Fluted Concrete Nails or Duro-Last #14 Concrete Screws spaced at 6" o.c. maximum, through the insulation and into

the deck.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 51 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Cementitious wood fiber attached with ¼-14 x 5-inch screws with 2-inch

diameter metal plates fastened 3 ½ inches from each edge and 8 inches o.c. between edge fasteners at each support spaced a maximum 32" o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 214 lbf when tested with Duro-Last Auger Fasteners installed through to the deck in

accordance with TAS 105.

System Type D(7): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density

Duro-Guard Iso II-A, Duro-Guard Iso II -H, Duro-Guard Iso II-G

Minimum 1.5" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last membrane or Duro-Tuff membrane shall be mechanically attached at

its minimum 6" tabs, spaced maximum 57" with Duro-Last Auger Fasteners & Plates spaced 6" o.c. maximum, through the insulation and into the deck. 6"

wide laps are sealed with a minimum 1.5" wide heat weld.

Or

Duro-Tuff membrane or Duro-Last EV membrane mechanically attached at its minimum 6" tabs, spaced maximum 57" with Polymer GypTec Fasteners and Polymer GypTech insulation plate spaced 6" o.c. maximum, through the insulation and into the deck. The 6" wide laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 52 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Cementitious wood fiber attached with ¼-14 x 5-inch screws with 2-inch

diameter metal plates fastened 3 ½ inches from each edge and 8 inches o.c. between edge fasteners at each support spaced a maximum 32" o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 250 lbf when tested with Duro-Last Auger Fasteners installed through to the deck in

accordance with TAS 105.

System Type D(8): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer Insulation Fasteners Fastener
(Table 3) Density

Duro-Guard Iso II-A, Duro-Guard Iso II –H, Duro-Guard Iso II-G Minimum 1.5" thick

N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last membrane or Duro-Tuff membrane shall be mechanically attached at

its minimum 6" tabs, spaced maximum 57" with Duro-Last Auger Fasteners & Plates spaced 6" o.c. maximum, through the insulation and into the deck. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 30 ft²/gal (two-sided application). 6"

wide laps are sealed with a minimum 1.5" wide heat weld.

Or

Duro-Tuff membrane or Duro-Last EV membrane mechanically attached at its minimum 6" tabs, spaced maximum 57" with Polymer GypTec Fasteners and Polymer GypTech insulation plate spaced 6" o.c. maximum, through the insulation and into the deck. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 30

ft²/gal

(two-sided application). The 6" wide laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 53 of 111

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 6-inches o.c. in the field. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 263 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in

accordance with TAS 105.

System Type D(9): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼" DensDeck, or

(Optional) ½" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener

Density

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso III-A,

Duro-Guard Iso II-H, Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners (Table 3) Fastener Density

Duro-Fold Underlayment Board

Minimum 0.375" thick N/A N/A

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H

Minimum 1" thick N/A N/A

Duro-Guard Iso II-G, Duro-Guard Iso HD-G, R-Tech Fan Fold, Duro-Guard EPS

Minimum 0.5" thick N/A N/A

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, DEXcell FA Glass Mat Roof Board Minimum 0.25" thick

N/A

N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 60" with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Poly-Plates or Cleat Plates paced 6" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 54 of 111

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached

with 0.113-inch x 2-3/8-inch ring shank nails fastened 6-inches o.c. at the perimeter and 6-inches o.c. in the field. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 600 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in

accordance with TAS 105.

System Type D(10): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼" DensDeck, or

(Optional) ½" SECUROCK

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener

Density

Any Approved EPS or XPS listed in Table 2, Duro-Guard Iso II-A, Duro-Guard Iso III-A,

Duro-Guard Iso II-H, Duro-Guard Iso III-H, Duro-Guard Iso II-G

Minimum ¹/₂" thick N/A N/A

Top Insulation Layer Insulation Fasteners (Table 3) Fastener

Density

Duro-Fold Underlayment Board

Minimum 0.375" thick N/A N/A

Duro-Guard Iso II-A, Duro-Guard Iso III-A, Duro-Guard Iso II-H,

Duro-Guard Iso III-H

Minimum 1" thick N/A N/A

Duro-Guard Iso II-G, Duro-Guard Iso HD-G, R-Tech Fan Fold

Minimum 0.5" thick N/A N/A

DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board, DEXcell FA Glass Mat Roof Board Minimum 0.25" thick

N/A

N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 120" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Poly-Plates or Cleat Plates paced 6" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -60 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 55 of 111

Deck Type 7I: Recover, Insulated

Deck Description:1. Min. 22 gage, Type B, Grade 80 steel deck with minimum ¹/₄" thick steel supports having a maximum span of 66 in. o.c.

2. Min. 20-18 gage, Type B, Grade 80 steel deck with minimum ¼" thick steel supports having a maximum span of 72 in. o.c.

Steel deck options listed above shall be fastened to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Sidelaps are attached with

Traxx/1 fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submitted Table.

System Type D(11): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density

Duro-Guard Iso II-A or Duro-Guard Iso II-H, Duro-Guard III-A,

H-Shield CG

Maximum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board, SECUROCK Gypsum Fiber Roof Board, DensDeck Prime Minimum 1/4" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Min. 50-mil Duro-Tuff membrane shall be mechanically attached maximum 12"

o.c. in rows spaced maximum 116" o.c. with Duro-Last Cleat Plates and Duro-Last #15 Extra Heavy Duty Drill Point Fastener. Laps are sealed with min. 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 56 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Min. 22 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel

supports having a maximum span of 6 ft. o.c. Deck attached to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Sidelaps are

attached with Traxx/1 fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(12): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer Insulation Fasteners (Table 3) Fastener

Density

Duro-Guard Iso II-A, Duro-Guard Iso II-H, Duro-Guard III-A,

H-Shield CG

Minimum 1" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Roof Board

Minimum ½" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum ¼" N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Min. 50-mil Duro-Tuff membrane shall be mechanically attached maximum 12"

o.c. in rows spaced maximum 56" o.c. with Duro-Last Cleat Plates and Duro-Last #15 Extra Heavy Duty Drill Point Fastener. Laps are sealed with min. 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 57 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Min. 22 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel

supports having a maximum span of 6 ft. o.c. Deck attached to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Side laps are

attached with Traxx/1 fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(13): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density
Duro-Guard Iso II-A, Duro-Guard Iso II-H, Duro-Guard II	I-A,	
H-Shield CG, Duro-Guard ISO HD-G		
Minimum 1" thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DensDeck Prime		
Minimum 1/4" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Min. 50-mil Duro-Tuff membrane shall be mechanically attached maximum 12"

o.c. in rows spaced maximum 56" o.c. with Duro-Last Cleat Plates and Duro-Last #15 Extra Heavy Duty Drill Point Fastener. Laps are sealed with min. 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 58 of 111

Deck Type 7I: Recover, Insulated

Deck Description:1. Min. 22 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel supports having a maximum span of 66 in. o.c.

2. Min. 20 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel supports having a maximum span of 72 in. o.c.

Steel deck options listed above fastened to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Side laps are attached with Traxx/1

fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(14): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer Insulation Fasteners (Table 3) Fastener

Density

Duro-Guard Iso II-A, Duro-Guard Iso II-H, Duro-Guard III-A,

H-Shield CG

Minimum 1" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density

DensDeck, SECUROCK Gypsum-Fiber Roof Board, SECUROCK Glass-Mat Roof Board Minimum ½" thick N/A N/A

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Min. 50-mil Duro-Tuff membrane shall be mechanically attached maximum 12"

o.c. in rows spaced maximum 116" o.c. with Duro-Last Cleat Plates and Duro-Last #15 Extra Heavy Duty Drill Point Fastener. Laps are sealed with min. 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 59 of 111

Deck Description: Min. 22 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel

supports having a maximum span of 6 ft. o.c. Deck attached to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Side laps are

attached with Traxx/1 fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(15): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso II-H, Duro-Guard III-A, Duro-Guard Iso III-H, ENRGY-3,

H-Shield, ISO 95+ GL, ACFoam II, ACFoam III, ACFoam IV, Duro-Guard Iso II-G

Minimum 1.5" thick 1 or 2 with 9 1:6.4 ft²

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS, Duro-Guard ISO HD-G Minimum ½" thick 1 or 2 with 9 1:6.4 ft²

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick 1 or 2 with 9 1:6.4 ft²

SECUROCK Gypsum Fiber Roof Board, DEXcell FA Glass Mat Roof Board, DensDeck Prime Minimum 1/4" thick 1 or 2 with 9 1:6.4 ft²

DEXcell Cement Roof Board

Minimum 7/16" thick 1 or 2 with 9 1:6.4 ft²

Note: Insulation layers above shall be mechanically attached with preliminary fastening as specified above. All Insulation panels shall also be mechanically fastened along with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, FR-

50® Fire Retardant Slip Sheet, ¼" Dens Deck, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core or a second sheet of barrier

board may be used over the insulation (see General Limitation #1).

Membrane Duro-Last® membrane shall be mechanically attached at its minimum 3" With 60" tabs: tabs, spaced maximum 60" o.c. with Duro-Last fasteners and Duro-Last Poly-plates® or Duro-Last Cleat Plates spaced 12" o.c. maximum, through

Poly-plates[®] or Duro-Last Cleat Plates spaced 12" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 60 of 111

Deck Description: Min. 22 gage, Type B, Grade 80 steel deck with minimum ¼" thick steel supports

having a maximum span of 6 ft. o.c. Deck attached to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Side laps are attached with

Traxx/1 fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(16): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

Any Approved EPS or XPS listed in Table 2

Minimum ½" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener
(Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso II-H, Duro-Guard III-A, Duro-Guard Iso III-H, ENRGY-3, H-Shield, ISO 95+ GL, ACFoam II, or ACFoam III, ACFoam IV, Duro-Guard Iso II-G

Minimum 1.5" thick

Minimum 1.5" thick 1 or 2 with 9 1:6.4 ft²

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS, Duro-Guard ISO HD-G Minimum ½" thick 1 or 2 with 9 1:6.4 ft²

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick 1 or 2 with 9 1:6.4 ft²

SECUROCK Gypsum Fiber Roof Board, DEXcell FA Glass Mat Roof Board, DensDeck Prime Minimum 1/4" thick 1 or 2 with 9 1:6.4 ft²

DEXcell Cement Roof Board

Minimum 7/16" thick 1 or 2 with 9 1:6.4 ft²

Note: Insulation layers above shall be mechanically attached with preliminary fastening as specified above. All Insulation panels shall also be mechanically fastened along with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, FR-

50® Fire Retardant Slip Sheet, $\frac{1}{4}$ " DensDeck, $\frac{1}{2}$ " thick UL Classification Type X Gypsum with a moisture resistant facer and core, Duro-Fold or a second sheet of barrier board may be used over the insulation (see General Limitation #1).

Membrane Duro-Last® membrane shall be mechanically attached at its minimum 3" tabs, With 28" tabs: spaced maximum 28" o.c. with Duro-Last #14 HD fasteners with Duro-Last

Poly-plates® or Duro-Last Cleat Plates spaced at 18" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat

weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 61 of 111

Deck Description: Minimum 22 gage, Grade 80 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 450 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in accordance with TAS 105. **This Tested Assembly has been analyzed for allowable deck stress. See**

Evidence Submitted Table.

System Type D(17): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density

Duro-Guard Iso II-H, Duro-Guard Iso III-H, Duro-Guard Iso III-A,

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Duro-Guard Iso HD-G, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS Minimum 0.5" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, DensDeck Prime

Minimum 0.25" thick N/A N/A

SECUROCK Gypsum Fiber Roof Board, DEXcell FA Glass Mat Roof Board, DensDeck Prime Minimum 1/4" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last Membrane with minimum 6-inch wide tabs spaced maximum 120-

inches o.c. shall be mechanically attached with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Poly-Plates or Cleat Plates fastened along the tab 6-

inches o.c. Minimum 1-inch wide heat weld at lap seams.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 62 of 111

Deck Description: Minimum 22 ga., Grade 33 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 263 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in accordance with TAS 105. **This Tested Assembly has been analyzed for allowable deck stress. See**

Evidence Submitted Table.

System Type D(18): All layers of insulation and base sheet simultaneously attached. Membrane

attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density

 $\textbf{Duro-Guard Iso II-H, Duro-Guard Iso III-H, Duro-Guard Iso III-A, Duro-Guard Iso III-$

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Duro-Guard Iso HD-G, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS Minimum 0.5" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, DensDeck Prime, DEXcell FA Glass Mat Roof Board Minimum 0.25" thick

N/A

N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: Insulation layer shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density (See Roofing Application Standard RAS 117 for fastening details).

Membrane: Duro-Last Membrane with minimum 6-inch wide tabs spaced maximum 60-

inches o.c. shall be mechanically attached with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Poly-Plates or Cleat Plates fastened along the tab 6-

inches o.c. Minimum 1-inch wide heat weld at lap seams.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 63 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Structural Concrete or Minimum 22 gage, Type B, Grade 80 steel deck attached

with ITW Buildex Traxx/4 or Traxx/5 fastener at a maximum spacing of 6" o.c., to minimum 1/4" thick steel supports having a maximum span of 6 ft. o.c. Sidelaps

are attached with Traxx/1 fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(19): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H. Duro-Guard HD-G

Minimum 1½" thick N/A N/A

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board, SECUROCK Gypsum Fiber Roof Board

Minimum ¼" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼"

DensDeck, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core, or a second sheet of barrier board may be used over the insulation

(see General Limitation #1).



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 64 of 111 Membrane: Duro-Last membrane, maximum 60" tabs, shall be mechanically attached at its

minimum 3" tabs, spaced every 60" with Duro-Last #14 HD fasteners and Duro-Last Poly-plates or Duro-Last Cleat Plates, or Duro-Last Fluted Concrete Nails (for structural concrete only) spaced 12" o.c. minimum, through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 65 of 111

Deck Type 7I: Recover, Insulated

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached 6"

o.c. with 8d common nails to support members. The wood deck shall record a Minimum Characteristic Resistance Force (MCRF) of 225 lbf when tested with Duro-Last #14 HD Fasteners in accordance with TAS 105. The existing roof

shall contain minimum 1" thick insulation.

System Type D(20): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-	3 25 PSI, Duro-Guard Iso II	[-G,
Duro-Guard II-H, Duro-Guard HD-G		
Minimum 1-1/2" thick	N/A	N/A
SECUROCK Gypsum-Fiber Roof Board, Cellofoam Typ Insulfoam EPS	pe IX EPS Insulation, Duro-	Guard EPS,
Minimum 1/2" thick	N/A	N/A
Kingspan GreenGuard Insulation Board CM		
Minimum 1" thick	N/A	N/A
DEXcell FA Glass Mat Roof Board		
Minimum 1/4" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 60"o.c. with Duro-Last #14 HD fasteners and Duro-Last Poly-Plates or Duro-Last Cleat Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Duro-last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal./ (two-sided application). Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 66 of 111

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached 6"

> o.c. with 8d common nails to support members. The wood deck shall record a Minimum Characteristic Resistance Force (MCRF) of 250 lbf when tested with Duro-Last #14 HD Fasteners in accordance with TAS 105. The existing roof

shall contain minimum 1" thick insulation.

System Type D(21): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H. Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, **Insulfoam EPS**

Minimum ½" thick N/A N/A Kingspan GreenGuard Insulation Board CM

Minimum 1" thick

N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum 1/4" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane, 57" tabs:

Duro-Last membrane shall be mechanically attached at its minimum 6" tabs, spaced maximum 57"o.c. with Duro-Last #14 HD fasteners with Duro-Last Cleat Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Duro-last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal. (two-sided application).

Laps are sealed with a minimum 1.5" wide heat weld.

or

Duro-Last membrane shall be mechanically attached at its minimum 6" tabs, spaced maximum 57"o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners with Duro-Last Duro-Last Cleat Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Fasteners are located 2.7-inches from tab edge. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 67 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Cementitious wood fiber deck attached to supports spaced a maximum 24" o.c.

with three (3) #15 fasteners and 2-inch diameter steel plates per panel, per support. The CWF deck should record a Minimum Characteristic Resistance Force (MCRF) of 214 lbf when tested with Duro-Last Liquid Auger Fastener through to the deck in accordance with TAS 105. The existing roof shall

contain minimum 1.5" thick insulation.

System Type D(22): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane, Duro-Tuff membrane or Duro-Last EV membrane shall be

mechanically attached at its minimum 6" tabs, spaced maximum 57"o.c. with Polymer GypTec fasteners with Polymer GypTec Insulation Plates or Duro-Last Auger Fastener and Auger Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat

weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 68 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Cementitious wood fiber deck attached to supports spaced a maximum 24" o.c.

with three (3) #15 fasteners and 2-inch diameter steel plates per panel, per support. The CWF deck should record a Minimum Characteristic Resistance Force (MCRF) of 285 lbf when tested with Duro-Last Liquid Auger Fastener through to the deck in accordance with TAS 105. The existing roof shall

contain minimum 1.5" thick insulation.3

System Type D(23): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS,

Insulfoam EPS

Minimum ½" thick N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane, Duro-Tuff membrane or Duro-Last EV membrane shall be

mechanically attached at its minimum 6" tabs, spaced maximum 57"o.c. with Polymer GypTec fasteners with Polymer GypTec Insulation Plate or Duro-Last Auger Fastener and Auger Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Duro-last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal./ (two-sided application). Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -60 psf. psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 69 of 111

Structural Concrete or Minimum 22 gage, type B, Grade 80 Steel attached to **Deck Description:**

supports having a maximum span of 6 ft. o.c. The deck should record a

Minimum Characteristic Resistance Force (MCRF) of 498 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) in accordance with TAS 105. The existing roof shall contain minimum 1" thick insulation. This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(24): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Laver Insulation Fasteners Fastener Density/ft² (Table 3)

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, **Insulfoam EPS**

Minimum ½" thick

N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum 1/4" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A Note: All layers of insulation and membrane shall be simultaneously attached. See membrane

below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 57" o.c., with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners(steel), Duro-Last #14 Concrete Screws or Duro-Last Concrete Nails (concrete), and Duro-Last Cleat Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Duro- Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal./ (two-sided application). Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -105 psf. (See General Limitation #7)

MIAMI-DADE COUNTY APPROVED

NOA No.: 17-0202.08 **Expiration Date: 08/22/22** Approval Date: 10/19/17 Page 70 of 111

Deck Description: Structural Concrete or Minimum 22 gage, type B, Grade 80 Steel attached to

supports having a maximum span of 6 ft. o.c. The deck should record a

Minimum Characteristic Resistance Force (MCRF) of 315 lbf when tested with Duro-Last #14 HD Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) in accordance with TAS 105. The existing

roof shall contain minimum 1" thick insulation.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(25): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum 1/4" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 84" o.c. with Duro-Last #14 HD Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) with Duro-Last Poly-plates or Duro-Last Cleat Plates spaced 6" o.c. maximum, through the insulation and/or LWC and into the deck. Laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 71 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Structural Concrete or Minimum 22 gage, type B, Grade 80 Steel attached to

supports having a maximum span of 6 ft. o.c. The deck should record a

Minimum Characteristic Resistance Force (MCRF) of 420 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) in accordance with TAS 105. The existing roof shall contain minimum 1" thick insulation.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(26): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of followings:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 3" tabs,

spaced maximum 84" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) with Duro-Last Cleat Plates or OMG Eyehook Accuseam Plate spaced 6" o.c. maximum, through the insulation and/or LWC

into the deck. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -60 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 72 of 111

Single Ply, PVC **Membrane Type:** Deck Type 7I: Recover, Insulated

Deck Description: Structural Concrete or Minimum 22 gage, type B, Grade 80 Steel attached to

supports having a maximum span of 6 ft. o.c. The deck should record a

Minimum Characteristic Resistance Force (MCRF) of 750 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) in accordance with TAS 105. The existing roof shall contain minimum 1" thick insulation. This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(27): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One of more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS,

Insulfoam EPS

Minimum ½" thick N/A N/A Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum 1/4" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 120" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel), Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) and Duro-Last Cleat Plates spaced 6" o.c. maximum, through the insulation and into the deck. Duro- Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal./ (two-sided application). Laps are sealed with a minimum 1.5" wide

heat weld.

Maximum Design

Pressure: -74 psf. (See General Limitation #7)

MIAMI DADE COUNTY APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 73 of 111

Deck Description: Structural Concrete or Minimum 22 gage, type B, Grade 80 Steel attached to

supports having a maximum span of 6 ft. o.c. The deck should record a

Minimum Characteristic Resistance Force (MCRF) of 367 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) in accordance with TAS 105. The existing roof shall contain minimum 1" thick insulation.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(28): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H. Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick

N/A

N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum ¼" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 57" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) with Duro-Last Cleat Plates spaced 12" o.c.

maximum, through the insulation and/or LWC and into the deck. Duro-Last Tab

Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal (two-sided application). Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 74 of 111

Deck Description: Structural Concrete or Minimum 22 gage, type B, Grade 80 Steel attached to

supports having a maximum span of 6 ft. o.c. The deck should record a

Minimum Characteristic Resistance Force (MCRF) of 367 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) in accordance with TAS 105. The existing roof shall contain minimum 1" thick insulation.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type D(29): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS,

Insulfoam EPS

Minimum ½" thick

N/A

N/A

N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

DEXcell FA Glass Mat Roof Board

Minimum ¼" thick N/A N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" wide

tabs, spaced maximum 84" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners (steel) or Duro-Last #14 Concrete Screws or Duro-Last Fluted Concrete Nails (concrete) with Duro-Last Cleat Plates spaced 6" o.c. maximum, through the insulation and/or LWC and into the deck. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal (two-sided application). Laps are sealed with a

minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 75 of 111

Deck Description: 1. Min. 22 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel

supports having a maximum span of 54 in. o.c.

2. Min. 20 gage, Type B, Grade 80 steel deck with minimum 1/4" thick steel

supports having a maximum span of 72 in. o.c.

Steel deck options listed above attached to supports with ITW Buildex Traxx/5 fastener at a maximum spacing of 6" o.c., Sidelaps are attached with Traxx/1

fasteners at 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submitted Table.

System Type D(30): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Base Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Any Approved EPS or XPS listed in Table 2

Minimum ½" thick

N/A

N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft²

Duro-Guard Iso II-A, Duro-Guard Iso II-H, Duro-Guard III-A, Duro-Guard Iso III-H, ENRGY-3, H-Shield, ISO 95+ GL, ACFoam II, or ACFoam III, Duro-Guard Iso IV-A, ACFoam IV, Duro-Guard Iso II-G

Minimum 1.5" thick 1 or 2 with 9 1:6.4 ft²

Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS, Duro-Guard ISO HD-G Minimum ½" thick 1 or 2 with 9 1:6.4 ft²

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick 1 or 2 with 9 1:6.4 ft²

DEXcell FA Glass Mat Roof Board, SECUROCK Gypsum Fiber Roof Board, DensDeck Prime Minimum 1/4" thick 1 or 2 with 9 1:6.4 ft²

DEXcell Cement Roof Board

Minimum 7/16" thick 1 or 2 with 9 1:6.4 ft²

Note: Insulation layers above shall be mechanically attached with preliminary fastening as specified above. All Insulation panels shall also be mechanically fastened along with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, FR-

50® Fire Retardant Slip Sheet, ¼" DensDeck, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core, Duro-Fold or a second sheet of barrier board may be used over the insulation (see General Limitation #1).

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 76 of 111



Membrane With 120" tabs

Duro-Last® membrane shall be mechanically attached at its minimum 3" tabs, spaced maximum 120" o.c. with Duro-Last fasteners with Duro-Last Polyplates® or Duro-Last Cleat Plates spaced at 6" o.c. maximum, through the insulation and into the deck. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 77 of 111

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft o.c. with 5/8-inch puddle welds at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 405 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed in accordance with TAS 105

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted.

System Type D(31): Membrane fastened over preliminarily fastened insulation. All layers

of insulation simultaneously attached.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
Duro-Guard ISO II-H,	,	•
Minimum 1" thick	N/A	N/A
Duro-Guard ISO II-G, Duro-Guard ISO HD-G		
Minimum ½" thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DEXcell H	FA Glass Mat Roof Board	
Minimum 1/4" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: Insulation layers above shall be mechanically attached with preliminary fastening. Insulation panels shall also be mechanically fastened with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Minimum 50-mil Duro-Last EV Membrane shall be mechanically attached 12"

o.c. in rows spaced 54" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Poly Plates. Minimum 6" wide laps are sealed with

minimum 1.5" heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 78 of 111

Deck Type 7I: Recover Deck, Insulated

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft o.c. with 5/8-inch puddle welds at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 428 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted.

System Type D(32): Membrane fastened over preliminarily fastened insulation. All layers

of insulation simultaneously attached.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Duro-Guard ISO II-H	,	·
Minimum 1" thick	N/A	N/A
Duro-Guard ISO II-G, Duro-Guard ISO HD-G		
Minimum ½" thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DEXcell FA Glas	s Mat Roof Board	
Minimum ¹ / ₄ " thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: Insulation layers above shall be mechanically attached with preliminary fastening. Insulation panels shall also be mechanically fastened ith the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Minimum 50-mil Duro-Last EV Membrane shall be mechanically attached 6"

o.c. in rows spaced 114" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point fasteners and Duro-Last Poly Plates. Minimum 6" wide laps are sealed with

minimum 1.5" heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 79 of 111

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft o.c. with 5/8-inch puddle welds at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 428 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted.

System Type D(33): Membrane fastened over preliminarily fastened insulation to existing single ply

membrane roof.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
Duro-Guard ISO II-H	,	•
Minimum 1" thick	N/A	N/A
Duro-Guard ISO II-G, Duro-Guard ISO HD-G		
Minimum ½" thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DEXcell FA Glas	ss Mat Roof Board	
Minimum 1/4" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: Insulation layers above shall be mechanically attached with preliminary fastening. Insulation panels shall also be mechanically fastened ith the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Minimum 50-mil Duro-Last EV Membrane shall be mechanically attached 6"

o.c. in rows spaced 114" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point fasteners and Duro-Last Poly Plates. Minimum 6" wide laps are sealed with

minimum 1.5" heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 80 of 111

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft o.c. with #12-24 x 1-1/4" HWH self-drilling screws fastened at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 428 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed in accordance

with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted.

System Type D(34): Membrane fastened over preliminarily fastened insulation. All layers

of insulation simultaneously attached.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Duro-Guard ISO II-H		•
Minimum 1" thick	N/A	N/A
Duro-Guard ISO II-G, Duro-Guard ISO HD-G		
Minimum ½" thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DEXcell FA Glas	s Mat Roof Board	
Minimum ¼" thick	N/A	N/A
DEXcell Cement Roof Board		
Minimum 7/16" thick	N/A	N/A

Note: Insulation layers above shall be mechanically attached with preliminary fastening. Insulation panels shall also be mechanically fastened with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Minimum 50-mil Duro-Last EV Membrane shall be mechanically attached 6"

o.c. in rows spaced 114" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point fasteners and Duro-Last Poly Plates. Minimum 6" wide laps are sealed with

minimum 1.5" heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 81 of 111

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft o.c. with 5/8-inch puddle welds at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 304 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted.

System Type D(35): Membrane fastened over preliminarily fastened insulation. All layers

of insulation simultaneously attached.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft ²
Duro-Guard ISO II-H, Duro-Guard ISO II-A	(Table 5)	Density/it
Minimum 1" thick	N/A	N/A
Duro-Guard ISO HD-G		
Minimum 1/2 " thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DensDeck Prime	e, DEXcell FA Glass Mat I	Roof Board
Minimum 1/4" thick	N/A	N/A

DEXcell Cement Roof Board

Minimum 7/16" thick N/A N/A

Note: Insulation layers above shall be mechanically attached with preliminary fastening. Insulation panels shall also be mechanically fastened with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Minimum 50-mil Duro-Last EV Membrane shall be mechanically attached 6"

o.c. in rows spaced 54" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Cleat Plates. Minimum 6" wide laps are sealed with

minimum 1.5" heat weld.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 82 of 111

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft o.c. with #12-24 x 1-1/4" HWH self-drilling screws fastened at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 338 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed in accordance

with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Insulation Fasteners

N/A

Fastener

N/A

evidence submitted.

System Type D(36): Membrane fastened over preliminarily fastened insulation. All layers

of insulation simultaneously attached.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following insulations:

·	(Table 3)	Density/ft ²
Duro-Guard ISO II-H, Duro-Guard ISO II-A Minimum 1" thick	N/A	N/A
Duro-Guard ISO HD-G Minimum 1/2 " thick	N/A	N/A
SECUROCK Gypsum Fiber Roof Board, DensDeck Prime, Minimum ¼" thick	, DEXcell FA Glass Ma N/A	at Roof Board N/A
DEXcell Cement Roof Board		

Note: Insulation layers above shall be mechanically attached with preliminary fastening. Insulation panels shall also be mechanically fastened with the roof membrane as specified below. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Minimum 50-mil Duro-Last EV Membrane shall be mechanically attached 6"

o.c. in rows spaced 54" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point fasteners and Duro-Last Cleat Plates. Minimum 6" wide laps are sealed with

minimum 1.5" heat weld.

Maximum Design

Minimum 7/16" thick

Insulation Layer

Pressure: -75 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 83 of 111

Deck Type 7I: Recover, Insulated

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached 6"

o.c. with 8d common nails to support members. The wood deck shall record a Minimum Characteristic Resistance Force (MCRF) of 600 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners in accordance with TAS

105.

System Type D(37): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas FR 10 loose laid

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

Duro-Guard EPS

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: Duro-Last membrane shall be mechanically attached 6" o.c. within a 6" wide

tab in rows spaced 120" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Cleat Plates or Poly Plates. Minimum 7-1/4" wide laps

are sealed with a minimum 1-1/4" heat weld.

Maximum Design

Pressure: -60 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 84 of 111

Deck Type 7I: Recover, Insulated

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached 6"

o.c. with 8d common nails to support members. The wood deck shall record a Minimum Characteristic Resistance Force (MCRF) of 263 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners in accordance with TAS

105.

System Type D(38): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Fire Barrier: Atlas FR 10 loose laid

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

Duro-Guard EPS

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: Duro-Last membrane shall be mechanically attached 6" o.c. within a 3" wide

tab in rows spaced 60" o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Cleat Plates or Poly Plates. Minimum 4-1/4" wide laps

are sealed with a minimum 1-1/4" heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 85 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Structural Concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 825 lbf when tested with Duro-Last #14 Concrete

Screw installed through to the deck in accordance with TAS 105.

System Type D(39): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layer.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer (Optional)

Insulation Fasteners
(Table 3)

Fastener
Density/ft²

AC Foam II, Duro-Guard ISO II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard ISO II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 120" o.c. with Duro-Last #14 Concrete Screw or Fluted

Concrete Nail with Duro-Last 3" Metal Plates fastened 6" o.c. in center of the 6" tab. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 60 ft²/gal (two-sided application).

Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 86 of 111

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached 6"

o.c. with 8d common nails to support members. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 250 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the

deck in accordance with TAS 105.

System Type D(40): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer (Optional) Insulation Fasteners Fastener

(Table 3) Posity/ft

(Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ¹/₂" thick N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board with no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 57"o.c. with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Cleat Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Fasteners are located 2.7" from the tab edge. Laps

are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 87 of 111

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached 6"

o.c. with 8d common nails to support members. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 250 lbf when tested with Duro-Last #14 HD Fasteners installed through to the deck in accordance with

TAS 105.

System Type D(41): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer (Optional) Insulation Fasteners Fastener

(Table 3) Density/ft²

AC Foam II, Duro-Guard Iso II-A, ENRGY-3, ENRGY-3 25 PSI, Duro-Guard Iso II-G,

Duro-Guard II-H, Duro-Guard HD-G

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

Kingspan GreenGuard Insulation Board CM

Minimum 1" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board with no dimension greater than 8 ft.

Membrane: Duro-Last membrane shall be mechanically attached at its minimum 6" tabs,

spaced maximum 57"o.c. with Duro-Last #14 HD Fasteners and Duro-Last 3" Metal Plates spaced a maximum of 6" o.c. through the insulation and into the deck. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 30 ft²/gal (two-sided application).

Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 88 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5

fasteners to supports having a maximum spacing of 6' o.c. Side laps secured

with Traxx1 fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

evidence submitted.

System Type D(42): All layers of insulation are preliminarily attached to roof deck as specified

below. Membrane is mechanically attached to deck through the insulation

layers.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of the following:

Insulation Layer Insulation Fasteners Fastener (Table 3) Fastener

AC Foam II, AC Foam III, H-Shield, ISO 95+ GL, Duro-Guard ISO II-A, ENRGY-3, Duro-Guard II-H, Duro-Guard HD-G,

Minimum 1-1/2" thick N/A N/A

SECUROCK Gypsum-Fiber Roof Board, Cellofoam Type IX EPS Insulation, Duro-Guard EPS, Insulfoam EPS

Minimum ½" thick N/A N/A

Note: All layers of insulation and membrane shall be simultaneously attached. See membrane below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft.

Membrane: Duro-Tuff membrane shall be mechanically attached at its minimum 4" wide

laps, spaced maximum 116" o.c., with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners and Duro-Last Cleat Plates spaced a maximum of 12" o.c. through the insulation and into the deck. Laps are sealed with a minimum 1.5"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)

MIAMI-DADE COUNTY

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 89 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Elastizell cellular lightweight concrete cast with Zell-Fibers in the mix, wet cast

density of 46-50 pcf, 354 psi compressive strength. Slurry coat, followed by 1" thick EPS Holey Board placed into the wet concrete, followed by a minimum 2" thick top coat of Elastizell cellular lightweight concrete cast over minimum 22

ga,

Grade 40, Type B, vented steel deck attached to supports at 7 ft. spans using ITW Buildex Traxx/5 fastners spaced 6" o.c. (each flue). Side laps attached with Buildex Traxx/1 fasteners spaced 20" o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 85 lbf when tested with Trufast Twin Loc-Nail Assembled Fasteners installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submitted Table.

System Type E(1): Anchor sheet mechanically fastened to LWC deck subsequent membrane adhered

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Anchor Sheet: JM PermaPly 28 or GAFGLAS #75 base sheet mechanically fastened with

Trufast Twin Loc-Nail Assembled Fasteners spacing of 7.5" o.c. at the 3" side

laps and 7.5" o.c. in two equally spaced staggered center rows.

Membrane: Duro-Last Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20

Adhesive applied using a splatter pattern at a rate of 7 lbs./square. Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 90 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached with

¼ inch x 2-inch self-tapping screws, staggered, 12-inches o.c. through the steel perimeter. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 525 lbf when tested with Duro-Last #14 HD Fasteners installed through to the wood support in accordance with TAS 105.

System Type E(2): Membrane mechanically attached through optional barriers to structural deck.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet, ¼"

DensDeck, ¼" SECUROCK, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core, or a second sheet of barrier board may be used

over the deck (see General Limitation #1).

Membrane: Duro-Last membrane shall be **mechanically attached into the wood supports** at

the minimum 6" tabs, spaced maximum 120" with Duro-Last #14 HD Fasteners and Duro-Last Poly-Plates or Cleat-Plates spaced 6" o.c. maximum. Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 91 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached with

¼ inch x 2 inch self-tapping screws, staggered, 12-inches o.c. through the steel perimeter. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 263 lbf when tested with Duro-Last #14 HD Fasteners installed through to the wood support in accordance with TAS 105.

System Type E(3): Membrane mechanically attached through optional barriers to structural deck.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet ®, ¼"

DensDeck, ¼" SECUROCK, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core, or a second sheet of barrier board may be used

over the deck (see General Limitation #1).

Membrane: Duro-Last membrane shall be **mechanically attached into the wood supports** at

the minimum 3" tabs, spaced maximum 60" with Duro-Last #14 HD Fasteners and Duro-Last Poly-Plates or Cleat-Plates spaced 6" o.c. maximum. Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 92 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: 19/32" plywood or wood plank with support at a maximum 24" o.c. attached with

½ inch x 2-inch self-tapping screws, staggered, 12-inches o.c. through the steel

perimeter. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 825 lbf when tested with Duro-Last #14 HD Fasteners installed through to the wood support in accordance with TAS 105.

System Type E(4): Membrane mechanically attached through optional barriers to structural deck.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Vapor Barrier: (Optional) Any UL or FM approved vapor barrier.

Fire Barrier: (Optional) Atlas Roofing Corporation FR-10®Fire Retardant Slip Sheet ®, ¼"

DensDeck, ¼" SECUROCK, ½" thick UL Classification Type X Gypsum with a moisture resistant facer and core, or a second sheet of barrier board may be used

over the deck (see General Limitation #1).

Membrane: Duro-Last membrane shall be **mechanically attached into the wood supports** at

the minimum 6" tabs, spaced maximum 120" o.c. with Duro-Last #14 HD Fasteners and Duro-Last Cleat-Plates spaced 6" o.c. maximum. Duro-Last Tab Sealer 4725 shall be applied over the tab membrane and to the overlying membrane underside at a rate of 30 ft²/gal (two-sided application). Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 93 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Minimum 22 ga., Grade 80 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 450 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(5): Membrane mechanically fastened to existing roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last Membrane with minimum 6 inch wide tabs spaced maximum 120

inches o.c. shall be fastened through existing roof into the deck with the fastener

and plate specified below.

Fastening: Membrane shall be fastened with Duro-Last #15 Extra Heavy Duty Drill

Point Fastener and Poly-Plates or Cleat Plates fastened along the tab maximum 6

inches o.c. Minimum 1-inch wide factory weld at the lap seams

Maximum Design

Pressure: -45 psf. (See General Limitation #7



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 94 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Poured gypsum concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 180 lbf when tested with Trufast Twin Loc Nail batten fasteners installed through to the deck in accordance with TAS 105.

System Type E(6): Membrane mechanically attached to roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last or Duro-Tuff membrane shall be mechanically attached 6" o.c. in rows

spaced 48" o.c. with 2-1/2" Duro-Last Auger Fasteners and Auger Plates or Trufast Twin Loc Coiled Batten bar and 1.8" Trufast Twin Loc Nail batten Fastener. A 10" wide cover strip welded over the fastener rows with a 1-1/2"

wide heat weld.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 95 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Minimum 22 ga., Grade 33 steel deck attached to supports having a maximum

span of 6 ft. o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 263 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(7): Membrane mechanically fastened to existing roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last Membrane with minimum 3 inch wide tabs spaced maximum 60

inches o.c. shall be fastened through existing roof into the deck with the fastener

and plate specified below.

Fastening: Membrane shall be fastened with Duro-Last #15 Extra Heavy Duty Drill

Point Fastener and Poly-Plates or Cleat Plates fastened along the tab maximum 6

inches o.c. Minimum 1-inch wide factory weld at the lap seams.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 96 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: The cementitious wood fiber panels attached to supports spaced maximum 4-ft.

o.c. with OMG Purlin fasteners with 2-inch metal plates, each panel is secured

with three (3) fasteners at each support. The CWF deck should record a

Minimum Characteristic Resistance Force (MCRF) of 338 lbf when tested with Duro-Last Auger Fasteners installed with Dow EnerFoam (See Fastening below

for details) through to the deck in accordance with TAS 105.

System Type E(8): Membrane mechanically fastened to existing roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last Membrane or Duro-Tuff membrane with minimum 1 inch wide weld

at lap seams shall be fastened through existing roof into the deck with the

fastener

and plate specified below.

Fastening: Duro-Last Auger Fastener with 2-inch diameter Auger Plates shall be installed 6"

o.c. in rows spaced a maximum 60" o.c. The fastener shall be embedded a

minimum 2-inches into the deck as follows: 1) 7/16" pilot hole drilled to a depth of 2.5"

2) Dow EnerFoam dispensed into the hole for two (2) full seconds using

application gun.

3) Fastener installed into the hole within 20-40 seconds after dispensing foam

Fastener rows shall be covered with a 10" wide strip for Duro-Last Membrane

and heat welded a minimum 1.5" along each edge to the roof membrane.

Maximum Design

Pressure: - 67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 97 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: The cementitious wood fiber panels attached to supports spaced maximum 4-ft.

o.c. with OMG Purlin fasteners with 2-inch metal plates, each panel is secured

with three (3) fasteners at each support. The CWF deck should record a Minimum Characteristic Resistance Force (MCRF) of 540 lbf when tested with Duro-Last Auger Fasteners installed with Dow EnerFoam (See Fastening below

for details) through to the deck in accordance with TAS 105.

System Type E(9): Membrane mechanically fastened to existing roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last Membrane or Duro-Tuff membrane with minimum 1 inch wide weld at

lap seams shall be fastened through existing roof into the deck with the fastener

and

plate specified below.

Fastening: Duro-Last Auger Fastener with 2-inch diameter Auger Plates shall be installed 6"

o.c. in rows spaced a maximum 96" o.c. The fastener shall be embedded a

minimum 2-inches into the deck as follows: 1) 7/16" pilot hole drilled to a depth of 2.5"

2) Dow EnerFoam dispensed into the hole for two (2) full seconds using

application gun

3) Fastener installed into the hole within 20-40 seconds after dispensing foam

Fastener rows shall be covered with a 10" wide strip for Duro-Last Membrane

and heat welded a minimum 1.5" along each edge to the roof membrane.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 98 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Poured gypsum concrete. The deck should record a Minimum Characteristic

Resistance Force (MCRF) of 165 lbf when tested with Trufast Twin-Loc Nail Batten Fastener installed through to the deck in accordance with TAS 105.

System Type E(10): Membrane mechanically attached to roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last or Duro-Tuff membrane shall be mechanically attached 3" o.c. in

rows spaced 48" o.c. with Trufast Twin Loc Coiled Batten bar and 1.8" Trufast Twin Loc Nail Batten Fastener. A 10" wide cover strip welded over the fastener

rows with a 1-1/2" wide heat weld.

Maximum Design

Pressure: -82.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 99 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5

fasteners to supports having a maximum spacing of 6' o.c. Side laps secured with Traxx 1 fasteners spaced 24" o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 428 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point fasteners installed through to the deck in

accordance with TAS 105

This Tested Assembly has been analyzed for allowable deck stress. See Evidence Submitted Table.

System Type E(11): Membrane mechanically attached to existing single ply membrane roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Tuff membrane shall be mechanically attached with Duro-Last #15 Extra

Heavy Duty Drill Point fasteners with Cleat Plates fastened 12" o.c. within 6"

wide laps spaced 114" o.c.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 100 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Minimum 22 ga., Type B, Grade 40 steel deck attached 6" o.c. with Traxx/5

fasteners to supports having a maximum spacing of 6' o.c. Side laps secured

with Traxx 1 fasteners spaced 24" o.c.

Or

Minimum 22 gage, Type B, Grade 40 steel deck attached to steel supports spaced 6 ft. o.c. with 5/8-inch puddle welds at each flute. No fasteners were

installed in the side laps.

The deck should record a Minimum Characteristic Resistance Force (MCRF) of 428 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners

installed through to the deck in accordance with TAS 105

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(12): Membrane mechanically attached to roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Tuff membrane shall be mechanically attached with Duro-Last #15 Extra

Heavy Duty Drill Point fasteners with Poly Plates or Cleat Plates fastened 6" o.c. Within 6" wide laps spaced 114" o.c. Fasteners are centered 1.25" from the

edge

of tab.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 101 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Min. 22 ga., Grade 33, Type B, Steel Deck attached 6" o.c. with Traxx/5

fasteners to supports having a maximum spacing of 6' o.c. Side laps secured with Traxx 1 fasteners spaced 24" o.c. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 304 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in

accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(13): Membrane mechanically attached to roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Tuff membrane shall be mechanically attached with Duro-Last #15 Extra

Heavy Duty Drill Point fasteners with Poly Plates or Cleat Plates fastened 6" o.c. within 6" wide laps spaced 54" o.c. Fasteners are centered 1.25" from the edge

of tab.

Maximum Design

Pressure: -67.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 102 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports

spaced 6 ft. o.c. with 5/8-inch puddle welds at each flute. No fasteners were installed in the side laps. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 236 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in accordance

with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(14): Membrane mechanically attached to roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Tuff membrane shall be mechanically attached with Duro-Last #15 Extra

Heavy Duty Drill Point fasteners with Poly Plates or Cleat Plates fastened 6" o.c. within 6" wide laps spaced 54" o.c. Fasteners are centered 1.25" from the edge

of tab.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 103 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: 19/32" plywood or wood plank with supports at a maximum 24" o.c. attached

with 0.113 inch x 2-3/8 inch ring shank nails fastened 6-inches o.c. at the perimeter and 12-inches o.c. in the field. The wood supports should record a Minimum Characteristic Resistance Force (MCRF) of 428 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the

wood support in accordance with TAS 105.

System Type E(15): Membrane mechanically attached to roof deck

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Tuff membrane shall be mechanically attached with Duro-Last #15 Extra

Heavy Duty Drill Point fasteners with Poly Plates or Cleat Plates fastened 6" o.c. within 6" wide laps spaced 114" o.c. Fasteners are centered 1.25" from the edge

of tab.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 104 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Min. 22 ga., Grade 80, Type B, Steel Deck attached 6" o.c. with #12-24 HWH

self drilling screws to supports having a maximum spacing of 6' o.c. No

fasteners

were installed at the side laps. The deck should record a Minimum

Characteristic Resistance Force (MCRF) of 450 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fasteners installed through to the deck in

accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(16): Membrane mechanically fastened to existing single ply roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturer's installation instructions.

Membrane: Duro-Last Membrane with minimum 1 inch wide weld at lap seams shall be

fastened through existing roof into the deck with the fastener and plate specified

below.

Fastening: Duro-Last #15 Extra Heavy Duty Drill Point Fastener and Poly Plates shall be

installed 6" o.c. within 6" wide tabs in rows spaced a maximum 120" o.c. with 1"

wide factory weld at lap seams.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 105 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Minimum 329 psi cellular lightweight concrete, with a wet cast density of 36-38

pcf, 1/8" Slurry coat, followed by 1" thick EPS Board placed into the wet

concrete, followed by a minimum 2" thick top coat cast after curing.

A minimum 26 ga, HD-Dek, vented , min. Grade 80, over structual supports spaced 5' o.c. with 5/8" diameter puddle welds with washers. Deck side laps stitched 15" o.c. with $\frac{1}{4}$ " – $14 \times 7/8$ " HWH screws. The deck should record a Minimum Characteristic Resistance Force (MCRF) of 225 lbf when tested with Duro-Last #15 Extra Heavy Duty Drill Point Fastener installed through to the

deck in accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(17): Membrane mechanically fastened to steel deck through existing single ply

membrane and LWC.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last Membrane with minimum 1-1/2 inch wide weld at lap seams shall be

fastened through existing roof and LWC into the steel deck with the fastener and

plate specified below.

Fastening: Duro-Last #15 Extra Heavy Duty Drill Point Fastener and Poly Plates shall be

installed 6" o.c. within 3" wide tabs in rows spaced a maximum 60" o.c. with

1-1/2" wide factory weld at lap seams.

Maximum Design

Pressure: -45 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 106 of 111

Deck Type 7I: Recover, Insulated

Deck Description: Minimum 22 ga., type B, Grade 33 steel deck with supports spaced maximum 6

ft. o.c. fastened with #12-24 HWH self drilling screws at each flute. Laps

stitched 24" o.c. with $\frac{1}{4}$ " – 14 x 7/8" HWH screws.

or

Minimum 22 gage, type B, Grade 33 steel deck attached to steel supports spaced 6 ft. o.c. with 5/8-inch puddle welds at each flute. Laps stitched 24"

o.c. with $\frac{1}{4}$ " – 14 x 7/8" HWH screws.

The deck should record a Minimum Characteristic Resistance Force (MCRF) of

420 lbf when tested with OMG XHD fasteners secured to the deck in

accordance with TAS 105.

This Tested Assembly has been analyzed for allowable deck stress. See

Evidence Submitted Table.

System Type E(18): Membrane induction welded to existing single ply membrane roof

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

<u>Duro-Bond Plate Note: When using Duro-Bond Plate 1302 over steel decks, ensure that the combined thickness of the existing roof assembly and new insulation is minimum 1". This thickness shall be measured from the top rib of the steel deck.</u>

Slip Sheet: (Optional) One ply of Duro-Blue Separation Slip Sheet or Duro-Weave

Separation Slip Sheet applied as per manufacturers installation instructions.

Membrane: Duro-Last membrane, Duro-Last EV membrane or Duro-Tuff membrane shall

be induction welded to Duro-Bond 1302 Plates in the manner and spacing

specified below.

Fastening: Membrane is welded to the Duro-Bond Plate 1302 with RhinoBond Welder.

The Duro-Bond 1302 Plates are secured at a rate of 1 per 4.0 ft². Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -52.5 psf. (See General Limitation #7)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 107 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Existing Smooth BUR, Granule SBS, Granule APP or Granule BUR over

structural concrete deck.

System Type F(1): Membrane directly adhered to existing roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20

Adhesive applied using a splatter pattern at a rate of 8 lbs./square. Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -370 psf. (See General Limitation #9)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 108 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Existing Smooth BUR, Granule SBS, Granule APP or Granule BUR over

structural concrete deck.

System Type F(2): Membrane directly adhered to existing roof system.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Duro-Fleece membrane or Duro-Fleece Plus membrane fully adhered

with Duro-Fleece CR-20 Adhesive applied using a splatter pattern at a rate of 8

lbs./square. Laps are sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -120 psf. (See General Limitation #9)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 109 of 111

Deck Type 7: Recover, Non-insulated

Deck Description: Existing Granule SBS, Granule APP or Granule BUR over

structural concrete deck.

System Type F(3): Membrane directly adhered to existing roof system

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Membrane: Duro-Fleece Plus membrane fully adhered with Duro-Fleece CR-20

Adhesive applied using a splatter pattern at a rate of 8 lbs./square. Laps are

sealed with a minimum 1.5" wide heat weld.

Maximum Design

Pressure: -150 psf. (See General Limitation #9)



NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 110 of 111

RECOVER SYSTEM LIMITATIONS:

- 1. All System Limitations and General Limitations shall apply. See specific deck type Notice of Acceptance for deck type System Limitations.
- 2. All assemblies listed herein shall be installed in compliance with the applicable sections of FBC 1521. Uplift performance of assemblies bonded to existing roofing system shall be verified per 1521.10. Uplift performance of assemblies mechanically attached through existing roofing system shall be verified per 1521.11.

GENERAL LIMITATIONS:

- 1. Fire classification is not part of this acceptance, refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each sidelap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq.

Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf. .

- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida Registered Engineer, Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117 and/or RAS 137. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform with Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 61G20-3 of the Florida Administrative Code.

END OF THIS ACCEPTANCE

MIAMI-DADE COUNTY
APPROVED

NOA No.: 17-0202.08 Expiration Date: 08/22/22 Approval Date: 10/19/17 Page 111 of 111