



- Note 1: Deck membrane shall be fastened around perimeter of roof penetration as per respective zone the skylight is located within (field, perimeter, corner).
- Note 2: Termination Bar shall have an approved Duro-Last fastener within 1 inch of each corner.
- Note 3: All field welds shall be a minimum of 1-1/2 inches wide.
- Note 4: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED: 04/28/2017	ROOF PENETRATION DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 12/03/2014	SKYLIGHT DECK MOUNT PENETRATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF