



Note 1: Pipe insulation must be continuous. Fill any gaps with urethane foam and tape closed.

Note 2: Lead flashings must be removed prior to installing Duro-Last Stack Flashings.

Note 3: Deck membrane shall be fastened around the perimeter of the Duro-Last Stack Flashing as per the respective zone the Duro-Last Stack Flashing is located within (field, perimeter, corner), no less than one fastener per flashing.

Note 4: All field welds shall be a minimum of 1-1/2 inches wide.

Note 5: Refer to specifications for vapor barrier, insulation and cover board requirements.

|                      |   |
|----------------------|---|
| REVISED: 02/02/2017  | ROOF PENETRATION DETAIL FOR MECHANICALLY FASTENED SYSTEMS |
| PREVIOUS: 01/01/2009 | INSULATED REFRIGERATION PIPE                              |
| SCALE: NONE          | NEW CONSTRUCTION OR RE-ROOF                               |