



Note 1: Refer to the *Roll Good Mechanically Fastened Roofing System* specification for the fastener spacing requirements on the wall and roof deck. Fastener spacing for wall membrane will be same as perimeter and corner fastening requirements for deck membrane.

Note 2: Overlap wall sheets a minimum of 6 inches.

Note 3: Tack weld the wall membrane to the roof membrane at the roof-to-wall transition between the roof membrane fasteners.

Note 4: All field welds shall be a minimum of 1-1/2 inches wide.

REVISED: 02/03/2017	PARAPET DETAIL FOR ROLL GOOD MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 08/01/2012	WALL FLASHING - HORIZONTAL FASTENING
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF